

[REDACTED]

From: Karen Garner
Sent: 16 October 2019 16:57
To: Planning Scanning
Subject: FW: *EXTERNAL: Proposed Ball Catch Netting - Felpham - Ball Stop Fencing FP/85/19/DOC
Attachments: Barratt_WL.pdf; Barratt_Sketch.pdf

[REDACTED]

Karen Garner | Post Approval Implementation and Monitoring Officer, Planning Department, Arun District Council |
Location: 1st Floor, Arun Civic Centre, Maltravers Road, Littlehampton, BN17 5LF

[REDACTED]

Visit Arun's web site at www.arun.gov.uk



Save the environment - think before you print.

From: Guzman, Kenny De [REDACTED]
Sent: 16 October 2019 09:36
To: Michael Eastham [REDACTED] Karen Garner [REDACTED]
Cc: Westcott, Malcolm [REDACTED]
Subject: FW: *EXTERNAL: Proposed Ball Catch Netting - Felpham - Ball Stop Fencing FP/85/19/DOC

Hi Michael/Karen,

Please find the attached specification of the ball stop fencing of the junior sports pitch and with the additional information below email. Thank you.

Kind Regards,

Kenny



BARRATT
DEVELOPMENTS PLC

Kenneth de Guzman
Assistant Technical Co-ordinator

[REDACTED]


 kenny.de.guzman@barratthomes.co.uk

<http://www.barrattddevelopments.co.uk>

BDW Southampton | Tollbar House | Tollbar Way

Hedge End | Southampton SO30 2UH

From [REDACTED]
Sent: 24 September 2019 12:35
To: McCormack, Connor [REDACTED]
Subject: *EXTERNAL: Proposed Ball Catch Netting - Felpham



EXTERNAL EMAIL WARNING

Please do not click on LINKS or ATTACHMENTS where you are unsure of its origin. In such cases delete the email.

Thank you once again for your recent enquiry in connection with the above.

We have great pleasure in submitting our proposal and quotation for your anticipated requirements as follows:

Budget Quotation BQ240919/1

Provide all necessary materials, labour, supervision, plant and equipment to supply and install 50 lineal metres of new 5 metre high Ball Catch Netting comprising:

- Posts: 5800 x 100 x 50 x 3.5 mm galvanised steel RHS sections, set 5 metres above and 800 mm below ground in 350 x 350 x 700 mm concrete foundation at 5 metre intervals
- Netting: 120 x 120 x 2.5 mm black, knotted, UV-stabilised football netting. Netting manufactured with outer overlapped edge seams plus an additional 3 no. horizontal seams for attaching to 5 no. galvanised steel linewires with stainless steel fencing clips.

For the total sum of £ 8,000.00

NOTES:

The posts and concrete foundations of our netting systems are structurally designed (BS6399 part 2) to take account of the wind loading at the site's particular location. Calculations can be made available without charge with order.

TERMS:

- Prices subject to a site visit as they are based upon good vehicle access and digging conditions throughout the fenceline
- Prices quoted exclude VAT
- Delivery 3-4 weeks from receipt of order
- Duration on site 4-6 working days (uninterrupted) to complete
- The identification of any underground or otherwise hidden cables, services, ducts or other voids to be the responsibility of the client. We will utilise our best endeavours but cannot be held responsible for any immediate and/or consequential losses for damage to any hidden apparatus.
- Payment due upon receipt of invoice following satisfactory completion

Please feel free to get back in touch if you require any additional information or clarification

Best Regards

Bernard J KilBride



Alfalfa Ltd t/as
ALPHAFENCE SPORTS & SECURITY FENCING
The Granary
Ty Coch
Upper Llanover

Abergavenny
NP7 9LA



NETTING SYSTEMS: Ball Catch Netting & Ball Stop Fencing; MUGA Roof Netting Systems; Retractable Dividing Nets; Demountable Netting; Tennis & Cricket Cages; Dust & Litter-Suppression Netting; Bird Control Netting

SPORTS FENCING: Twin Wire Panel Systems; Weldmesh & Chainlink; Plywood & 358 Rebound Fencing, Timber Kick Boards; Hockey, Football, 5-a-Side Fencing; Drag Mats & Boot Brushes; Spectator Buildings.

SECURITY FENCING: Palisade Fencing; Single Wire 3D Panel Fencing; 358 Prison Mesh; Vertical Bar, Bow Top & Ornamental Steel Railings; Weldmesh Fencing; Bin, Bike & Gas Storage Cages; Swing & Sliding Gates; Handrails; Acoustic Fencing; Razor Wire & Anti-Scaling Systems

WARNING: Although the company has taken reasonable precautions to ensure no viruses or malware are present in this email, the company cannot accept responsibility for any loss or damage arising from the use of this email or attachments.

Alfalfa Ltd is a limited company number 06555658 whose registered address is The Granary, Ty Coch, Upper Llanover, Abergavenny, NP7 9LA. Company is registered in England & Wales.

The sender of this e-mail is a member of the Barratt Developments PLC group of companies, the ultimate parent of which is Barratt Developments PLC (company number 00604574). Barratt Developments PLC is registered in England and Wales with its registered office at Barratt House, Cartwright Way, Forest Business Park, Bardon Hill, Coalville, Leicestershire LE67 1UF, together with its principal subsidiaries BDW Trading Limited (03018173), and Wilson Bowden Developments Limited (00948402). Barratt Homes, Barratt London and David Wilson Homes are trading names of BDW Trading Limited. This e-mail message is meant only for use by the intended addressee and may contain privileged and/or confidential information. If you have received this message in error please notify us and remove it from your system. Please view our 'Email Addendum v2.0' at www.barrattcommercialsupport.co.uk/barratt-developments-plc-email-a for further details.