
















38a High Street
Alton
Hampshire
GU34 1BD
T : 01420 593250
F : 01420 544243
E : studio@fabrikuk.com
F : 01420 544243

Hard Landscape					
Paving Type 1 - PCC Block Paving Colour/Size: Brindle 200 x 100 x 50mm Bond: 80° Herringbone  PT1a	Paving Type 4 - PCC Slab Paving Product: Conservation Kerb Colour/Size: Natural 600 x 450 x 50mm Bond: Stack  PT4	Kerb Type 4 - PCC Drop Road Kerb Product: Conservation Kerb Colour/Size: Silver Grey 255 x 250 x length  DK 4	Boundary Type 4 - Double Leaf Gates To Architects specification  PG	Other Existing Trees and Vegetation to be retained to be retained and protected, refer to arboricultural impact Assessment & Method Statement prepared by ADC for detail 	
Paving Type 1a - PCC Permeable Block Paving Colour/Size and Bond: To match PT1  PT1a	Paving Type 5 - Setts Product: Granite Setts Colour/Size: Natural 100 x 100 x 100mm  PT5	Kerb Type 1 - PCC Road Kerb Product: Conservation Kerb Colour/Size: Natural 100 x 100 x 100mm  1	Boundary Type 1 - Close Boarded Fence Product: Jacksons Close Board Fence Height: 1.5m  PG	Private Garden To be cleared & graded 	
Paving Type 2 - PCC Slab Paving Colour/Size: Buff 440 x 450 x 50mm Bond: Stretcher  PT2	Kerb Type 2 - PCC Road Kerb Product: Conservation Kerb Colour/Size: Silver Grey 255 x 205 x length  2	Boundary Type 2 - Brick Wall Height: 1.5m To Architects detail and specification  2	Garden Shed 	Existing Trees and vegetation to be removed Refer to arboricultural Impact Assessment & Method Statement prepared by ADC for detail 	
Paving Type 3 - Tarmac Product: Tarmac - Local Source Colour: Black  PT3	Kerb Type 2 - PCC Edging Product: Conservation Edging Colour/Size: Silver Grey 63 x 150 x length  2	Boundary Type 3 - Kone Rail Product: Jacksons Diamond Rail Fence Height: 0.9m  3	Reclaimed Area Boundary 	Root Protection Zone Refer to arboricultural Impact Assessment & Method Statement prepared by ADC for detail 	
Paving Type 3 - Permeable Tarmac Product: Permeable Tarmac to match PT3 Colour: to match PT3  PT3a	Kerb Type 3 - PCC Block Header Course Product: to match PT1 Colour/Size: Brindle and White / to match PT1  3	Boundary Type 4 - Single Leaf Gates To match adjacent fencing  4			

External References:

- D1530/Drawings/Planning Consultant/Recvd-16-08-08 Replan Boundaries/SITE LAYOUT PH 4 S REPLAN_31 - Copy.dwg
- D1530/Drawings/Tree Survey/Recvd-16-08-08/BDWS19795-03Dex_COPY.dwg

B. 09.08.16 Minor amendments to boundary treatment and cycle path and co-ordinated latest tree survey to suit Tree Officer's comments. CLB

A. 09.09.15 In response to Architect's comments ME

No. Date Reason Name

Project
Felpham, Bognor Regis
for Barratt Homes

Drawing
Hard General Arrangement
Phase 4/5 Replanned areas

Scale	Date
1 : 250@A0	Sept 15
Drawing No.	
D1530.L.281	
☐ Preliminary ☒ Issued for Planning Approval ☐ Issued for Construction	
Drawing sheet size - A0	

Drawn
me
Revision
B