

ST MARY'S MEADOW TREE SCHEDULE					
NO.	SPECIES	COMMON NAME	SIZE	POT SIZE	COMMENTS
1	ACER campestre	Field maple	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem
2	ACER platanoides	Norway maple	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
3	AESULUS hippocastanum	Horse chestnut	20-25cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem, even canopy
4	BETULA pendula	Silver birch	20-25cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
5	CARPINUS betulus	Hornbeam	18-20cm grth	Rootballed	3x transplanted, feathered, 4-4.5m high, even canopy
6	CASTANEA sativa	Sweet chestnut	18-20cm grth	Rootballed	3x transplanted, 4.5m high, min. 2m clear stem, even canopy
7	CRATAEGUS monspina	Common Hawthorn	18-20cm grth	Rootballed	3x transplanted, 4.5m high, min. 2m clear stem
8	FAGUS sylvatica	Common beech	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
9	FRAXINUS excelsior	Crab apple	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
10	MALUS domestica	Flowering crab	18-20cm grth	Rootballed	3x, min. 4.5m high, 1.75-2m clear stem
11	PINUS sylvestris	Scots pine	14-16cm grth	Container	3x, leader/lateral
12	POPULUS nigra	Black poplar	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem
13	PRUNUS avium	Wild cherry	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem, even canopy
14	PRUNUS domestica	Pear, 'Chandler'	18-20cm grth	Rootballed	3x, 4-5.5m high, min. 2m clear stem
15	QUERCUS ilex	Horn Oak	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem, even canopy
16	QUERCUS robur	Common oak	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
17	SORBUS aria	Whitebeam	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
18	SORBUS aucuparia	Fm. Whitebeam	18-20cm grth	Rootballed	3x, 4-4.5m high, min. 2m clear stem
19	SORBUS torminalis	New Horizon Elm	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem, even canopy
20	TILIA cordata	Small leaved lime	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem

ARUN WAY TREE SCHEDULE					
NO.	SPECIES	COMMON NAME	SIZE	POT SIZE	COMMENTS
1	ACER campestre	Field maple	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem
2	ACER campestre 'William Caldwell'	Fm. Field maple	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem, even canopy
3	ACER platanoides	Norway maple	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
4	ACER pseudoplatanus	Sycamore	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
5	AESULUS hippocastanum	Horse chestnut	20-25cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
6	BETULA pubescens	Downy birch	20-25cm grth	Rootballed	3x transplanted, 4.5m high, min. 2m clear stem
7	CARPINUS betulus	Hornbeam	18-20cm grth	Rootballed	3x transplanted, feathered, 4-4.5m high, even canopy
8	CARPINUS betulus 'Lucas'	Fm. Hornbeam	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
9	CRATAEGUS laevigata 'Paul's Scarlet'	Fm. Hawthorn	18-20cm grth	Rootballed	3x transplanted, 3.5-4.25m high, 1.75-2m clear stem, even canopy
10	CRATAEGUS laevigata	Common Hawthorn	18-20cm grth	Rootballed	3x transplanted, 3.5-4.25m high, 1.75-2m clear stem
11	CRATAEGUS monspina	Common Hawthorn	18-20cm grth	Rootballed	3x transplanted, 4.5m high, min. 2m clear stem
12	FAGUS sylvatica	Common beech	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
13	FAGUS sylvatica 'Purpurea'	Purple beech	20-25cm grth	Rootballed	3x4x5 transplanted, 4.5-5m high, min. 2m clear stem, even canopy
14	MALUS domestica	Crab apple	18-20cm grth	Rootballed	3x transplanted, min. 4.25m high, 1.75-2m clear stem
15	MALUS sylvestris	Flowering crab	18-20cm grth	Rootballed	3x, min. 4.5m high, 1.75-2m clear stem
16	PINUS sylvestris	Scots pine	14-16cm grth	Container	3x, leader/lateral
17	POPULUS nigra	Black poplar	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem
18	PRUNUS avium	Wild cherry	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem, even canopy
19	PRUNUS domestica	Pear cherry	18-20cm grth	Rootballed	3x transplanted, 4.25-5m high, min. 2m clear stem, even canopy
20	QUERCUS robur	Common oak	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
21	SORBUS aria	Whitebeam	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
22	SORBUS aucuparia	Rowan	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
23	TILIA cordata	Small leaved lime	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem

ST MARY'S MEADOW TREE SCHEDULE					
NO.	SPECIES	COMMON NAME	SIZE	POT SIZE	COMMENTS
1	ACER campestre	Field maple	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem
2	ACER pseudoplatanus	Sycamore	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
3	AESULUS hippocastanum	Horse chestnut	20-25cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
4	BETULA pendula	Silver birch	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
5	CARPINUS betulus	Hornbeam	18-20cm grth	Rootballed	3x transplanted, feathered, 4-4.5m high, even canopy
6	CRATAEGUS laevigata 'Paul's Scarlet'	Fm. Hawthorn	12-14cm grth	Rootballed	3x transplanted, 3.5-4.25m high, 1.75-2m clear stem, even canopy
7	CRATAEGUS monspina	Common Hawthorn	18-20cm grth	Rootballed	3x transplanted, 4.5m high, min. 2m clear stem
8	FAGUS sylvatica	Common beech	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
9	FAGUS sylvatica 'Purpurea'	Purple beech	20-25cm grth	Rootballed	3x4x5 transplanted, 4.5-5m high, min. 2m clear stem, even canopy
10	MALUS domestica	Crab apple	18-20cm grth	Rootballed	3x transplanted, min. 4.25m high, 1.75-2m clear stem
11	MALUS sylvestris	Flowering crab	18-20cm grth	Rootballed	3x, min. 4.5m high, 1.75-2m clear stem
12	PINUS sylvestris	Scots pine	14-16cm grth	Container	3x, leader/lateral
13	POPULUS nigra	Black poplar	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem
14	PRUNUS avium	Wild cherry	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem, even canopy
15	PRUNUS domestica	Pear cherry	18-20cm grth	Rootballed	3x transplanted, 4.25-5m high, min. 2m clear stem, even canopy
16	QUERCUS robur	Common oak	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
17	SORBUS aria	Whitebeam	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
18	SORBUS aucuparia	Rowan	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
19	TILIA cordata	Small leaved lime	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem

RYEBANK TREE SCHEDULE					
NO.	SPECIES	COMMON NAME	SIZE	POT SIZE	COMMENTS
1	ACER campestre	Field maple	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem
2	ACER pseudoplatanus	Sycamore	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
3	AESULUS hippocastanum	Horse chestnut	20-25cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
4	ANUS cordata	Italian alder	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
5	CARPINUS betulus	Common alder	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
6	BETULA pubescens	Downy birch	Multi-stem	Rootballed	20x transplanted, 4.4-5m high, multi-stem
7	CARPINUS betulus 'Lucas'	Common white birch	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem, even canopy
8	CORVUS avellana	Common hazel	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
9	CRATAEGUS laevigata	Midland Hawthorn	12-14cm	Rootballed	20x transplanted, 2.5-3m high, multi-stem
10	CRATAEGUS monspina	Common Hawthorn	18-20cm grth	Rootballed	3x transplanted, 3.5-4.25m high, 1.75-2m clear stem
11	FAGUS sylvatica	Common beech	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
12	FAGUS sylvatica 'Purpurea'	Purple beech	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem, even canopy
13	MALUS sylvestris	Crab apple	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, 1.75-2m clear stem
14	MALUS sylvestris	Flowering crab	18-20cm grth	Rootballed	3x, min. 4.5m high, 1.75-2m clear stem
15	PRUNUS avium	Wild cherry	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem, even canopy
16	PRUNUS domestica	Pear cherry	14-16cm grth	Rootballed	3x transplanted, 4.25-5m high, min. 2m clear stem, even canopy
17	QUERCUS robur	Common oak	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
18	SALIX alba var. 'vitellina 'Britzensis'	Scotish willow	multi-stem	Rootballed	20x transplanted, 2.5-3m high, multi-stem
19	SALIX caprea	Goat willow	18-20cm grth	Rootballed	3x, 4.5-5m high, min. 2m clear stem
20	SORBUS aria	Whitebeam	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
21	SORBUS aucuparia	Whitebeam	18-20cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem
22	TILIA cordata	Small leaved lime	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem

CLIPPING EDGE TREE SCHEDULE					
NO.	SPECIES	COMMON NAME	SIZE	POT SIZE	COMMENTS
1	ACER campestre	Field maple	20-25cm grth	Rootballed	3x4x5 transplanted, 5-5.5m high, min. 2m clear stem
2	ACER pseudoplatanus	Sycamore	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem
3	BETULA pendula	Silver birch	20-25cm grth	Rootballed	4x, 5-5.5m high, min. 2m clear stem, even canopy
4	CARPINUS betulus	Hornbeam	18-20cm grth	Rootballed	3x transplanted, feathered, 4-4.5m high, even canopy
5	FAGUS sylvatica	Common beech	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
6	JUGLANS regia	Common walnut	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem
7	MALUS sylvestris	Flowering crab	18-20cm grth	Rootballed	3x, min. 4.5m high, 1.75-2m clear stem
8	PINUS sylvestris	Scots pine	14-16cm grth	Container	3x, leader/lateral
9	PRUNUS avium	Wild cherry	18-20cm grth	Rootballed	3x transplanted, 4.5-5m high, min. 2m clear stem, even canopy
10	PRUNUS domestica	Pear, 'Chandler'	18-20cm grth	Rootballed	3x, 4.5-5m high, min. 2m clear stem
11	QUERCUS ilex	Horn Oak	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem, even canopy
12	SORBUS torminalis	Wild Service tree	18-20cm grth	Rootballed	3x, 4-5.5m high, min. 2m clear stem
13	TILIA cordata	Fm. Small leaved lime	20-25cm grth	Rootballed	3x4x5, 5-5.5m high, min. 2m clear stem

ST MARY'S MEADOW & ARUN WAY PUBLIC OPEN SPACE PLANTING SCHEDULE						
%	LATIN NAME	COMMON NAME	SIZE	POT SIZE	CENTRES	COMMENTS
NATIVE WOODLAND STRUCTURE PLANTING						
To be planted on a staggered grid at 1.5m, 3m and 6m cts. Planted in species groups of 3, 5 and 7.						
20	ACER campestre	Field maple	10-12cm grth	Bareroot	6000mm	2x transplanted, 4 breaks, min. 3-3.5m high with min. 1.75-2m clear stem
20	JUGLANS regia	Walnut	10-12cm grth	Bareroot	6000mm	2x transplanted, 4 breaks, min. 3-3.5m high with min. 1.75-2m clear stem
25	PINUS sylvestris	Scots Pine	10-12cm grth	Bareroot	6000mm	2x transplanted, min. 2.5-3m high
25	QUERCUS robur	Common oak	10-12cm grth	Bareroot	6000mm	2x transplanted, 4 breaks, min. 3-3.5m high with min. 1.75-2m clear stem
20	ACER campestre	Field maple	175-200cm	Bareroot	3000mm	Feathered 2x transplanted, branched, min. 5 breaks
20	CRATAEGUS monspina	Hawthorn	175-200cm	Bareroot	3000mm	Feathered 2x transplanted, branched, min. 5 breaks
10	ILEX aquifolium	Holly	175-200cm	Rootball	3000mm	Leader/lateral
20	PINUS sylvestris	Scots Pine	175-200cm	Rootball	3000mm	Feathered 2x transplanted
10	PRUNUS avium	Wild cherry	175-200cm	Bareroot	3000mm	Feathered 2x transplanted, branched, min. 5 breaks
10	SORBUS aria	Rowan	175-200cm	Bareroot	3000mm	Feathered 2x transplanted, branched, min. 5 breaks
15	CARPINUS betulus	Hornbeam	60-80cm	Bareroot	1500mm	1+1 or 1/1
25	CRATAEGUS monspina	Hawthorn	60-80cm	Bareroot	1500mm	1+1 or 1/1
10	CORVUS avellana	Hazel	60-100cm	Bareroot	1000mm	1+2 or 1/2, min. 3 branched
5	CORVUS avellana	Hazel	60-100cm	Bareroot	1000mm	1+1 or 1/1, branched, min. 2 breaks
5	ELONYMUS europaeus	Sandale	60-80cm	Bareroot	1000mm	1+1 or 1/1, branched, min. 2 breaks
5	ELONYMUS europaeus	Common holly	60-80cm	Rootball	1000mm	1+2 or 1/2, branched, min. 2 breaks
10	ILEX aquifolium	Common holly	60-80cm	Rootball	1000mm	Leader/lateral
10	PRUNUS avium	Wild cherry	60-80cm	Bareroot	1500mm	1+1 or 1/1, branched, min. 2 breaks
5	MALUS sylvestris	Crab Apple	60-80cm	Bareroot	1500mm	1+1 or 1/1, branched, min. 2 breaks
5	PRUNUS avium	Wild cherry	60-80cm	Bareroot	1500mm	1+1 or 1/1
5	SALIX purpurea	Purple Willow	60-80cm	Bareroot	1000mm	1+2 or 1/2, branched, min. 3 breaks
5	VIBURNUM opulus	Guelder rose	60-80cm	Bareroot	1500mm	1+2 or 1/2, min. 3 branched

NATIVE HEDGE						
To be planted at minimum double staggered, 1m between rows at 1m cts. Planted in species groups of 3, 5 and 7.						
Feathered						
10	ACER campestre	Field maple	150-180cm	Bareroot	1000mm	2x feathered, min. 4 breaks
20	CRATAEGUS monspina	Hawthorn	150-180cm	Bareroot	1000mm	2x feathered, min. 4 breaks
10	FAGUS sylvatica	Beech	150-180cm	Bareroot	1000mm	2x feathered, min. 4 breaks
10	PINUS sylvestris	Scots Pine	150-180cm	Rootball	1000mm	2x feathered
10	CORVUS avellana	Hazel	80-100cm	Bareroot	1000mm	1+2, min. 3 breaks
5	CORVUS avellana	Hazel	80-100cm	Bareroot	1000mm	1+2 or 1/2, min. 3 breaks
5	CRATAEGUS monspina	Hawthorn	80-100cm	Bareroot	1000mm	1+2 or 1/2, branched
5	ELONYMUS europaeus	Sandale	80-100cm	Bareroot	1000mm	1+1 or 1/1, branched
5	ILEX aquifolium	Common holly	80-100cm	Rootball	1000mm	Leader/Lateral
10	PRUNUS avium	Wild cherry	80-100cm	Bareroot	1000mm	1+2 or 1/2, branched, min. 3 breaks
5	MALUS sylvestris	Russet Rose	80-100cm	Bareroot	1000mm	1+1, branched, min. 3 breaks
5	SALIX purpurea	Purple Willow	80-100cm	Bareroot	1000mm	1+2 or 1/2, branched, min. 3 breaks
NATIVE SCRUB PLANTING						
To be planted on a staggered grid at 1m cts. Planted in species groups of 3, 5 and 7.						
20	CORVUS avellana	Hazel	80-100cm	Bareroot	1000mm	1+2 or 1/2, min. 3 breaks
5	CORVUS avellana	Hazel	80-100cm	Bareroot	1000mm	1+2 or 1/2, min. 3 breaks
5	CRATAEGUS monspina	Hawthorn	80-100cm	Bareroot	1000mm	1+2 or 1/2, branched
5	ELONYMUS europaeus	Sandale	80-100cm	Bareroot	1000mm	1+1 or 1/1, branched
10	ILEX aquifolium	Common holly	80-100cm	Rootball	1000mm	Leader/Lateral
10	PRUNUS avium	Wild cherry	80-100cm	Bareroot	1000mm	1+2 or 1/2, branched, min. 3 breaks
5	MALUS sylvestris	Russet Rose	80-100cm	Bareroot	1000mm	1+1, branched, min. 3 breaks
5	SALIX purpurea	Purple Willow	80-100cm	Bareroot	1000mm	1+2 or 1/2, branched, min. 3 breaks
5	VIBURNUM opulus	Guelder Rose	80-100cm	Bareroot	1000mm	1+2 or 1/2, branched, min. 3 breaks

LANDINGS GREEN PUBLIC OPEN SPACE PLANTING SCHEDULE						
%	LATIN NAME	COMMON NAME	SIZE	POT SIZE	CENTRES	COMMENTS
NATIVE WOODLAND STRUCTURE PLANTING						
To be planted on a staggered grid of 1.5m, 3m and 6m cts. Planted in species groups of 3, 5 and 7.						
Standard						
20	ACER campestre	Field maple	10-12cm grth	Bareroot	600mm	2x transplanted, 4 breaks, min. 3-3.5m high with min. 1.75m clear stem
20	AULAGASTRUM nemorosum	Wood anemone	10-15cm grth	Bareroot	600mm	2x transplanted, 4 breaks, min. 3-3.5m high with min. 1.75m clear stem
25	PRUNUS avestras	Scots Pine	10-12cm grth	Bareroot	600mm	2x transplanted, min. 4-5m high
25	QUERCUS robur leafed	Common oak	10-12cm grth	Bareroot	600mm	2x transplanted, 4 breaks, min. 3-3.5m high with min. 1.75m clear stem
20	ACER campestre	Field maple	175-200cm	Bareroot	3000mm	Feathered 2x transplanted, branched, min. 3 breaks
20	AGNUS VULGARIS nemorosum	Wood anemone	175-200cm	Bareroot	3000mm	Feathered 2x transplanted, branched, min. 3 breaks
20	ILEX aquifolium	Holly	175-200cm	Rootball	3000mm	Leader/Lateral
20	PRUNUS avestras	Scots Pine	175-200cm	Rootball	3000mm	Feathered 2x transplanted
20	PRUNUS avium	Wild cherry	175-200cm	Bareroot	3000mm	Feathered 2x transplanted, branched, min. 3 breaks
15	SORBUS aucuparia	Rosin	175-200cm	Bareroot	3000mm	Feathered 2x transplanted, branched, min. 3 breaks
Transplanted						
15	CARPINUS betulus	Hornbeam	60-80cm	Bareroot	1500mm	1x 1st yr, 1x 1st
15	CRATAEGUS monspeliensis	Hawthorn	60-80cm	Bareroot	1500mm	1x 1st yr, 1x 1st
15	CORYLUS avellana	Hazel	60-80cm	Bareroot	1500mm	1x 12 yr, 12 yr, 1 branch
3	CORYLUS masculina	Hazel	60-80cm	Bareroot	1500mm	1x 1st yr, 1x 1st, branched, min. 2 breaks
15	QUERCUS robur	Common oak	60-80cm	Bareroot	1500mm	1x 1st yr, 1x 1st, branched, min. 2 breaks
15	ILEX aquifolium	Common holly	60-80cm	2L	1500mm	Leader/Lateral
15	PRUNUS avestras	Scots Pine	60-80cm	Bareroot	1500mm	1x 1st yr, 1x 1st, branched, min. 2 breaks
10	PRUNUS laurocerasus	Blackthorn	60-80cm	Bareroot	1500mm	1x 1st yr, 1x 1st
5	SALIX purpurea	Purple Willow	60-80cm	Bareroot	1500mm	1x 12 yr, 12 yr, branched, min. 3 breaks
5	FRAXINUS excelsior	Common ash	60-80cm	Bareroot	1500mm	1x 1st yr, 1x 1st