



- RM1 Boundary
- Timber closeboard fence 1.8m high
- Timber closeboard gate 1.8m high
- Timber post and wire fence 1.2m high
- Cleft chestnut post and rail fence 1.2m high
- Secondary and Tertiary Streets (incl parking bays / driveways): Macadam surface road
- Street Kerb/edging: Charcon British Standards BN Kerb 145x255mm 125mm upstand
- Mews Street: Charcon Woburn Rumbled in Autumn, 200x134, 45deg herringbone Kerb/edging: Charcon Eco Countryside Kerb 145x255, 50mm upstand
- Driveways: Charcon Woburn Rumbled in Autumn, 200x134, stretcher bond
- Thresholds: Charcon Eco Countryside, 220x100, stretcher bond
- Public footpaths/Cycleway: Macadam surface Kerb/edging: Charcon British Standard Flat Top, 50x250mm, laid flush
- Private footpaths: Charcon Stonemaster Flag, 450x450mm in sandy buff, stack bond
- POS footpath: Compacted hoggin
- Timber Seat
- Extent of equipped and natural play area (Refer to RM1-XX-DR-L-P-025 for further information on play provision)

Section 1:100

0 5 10 m



tor
&CO

Everdene House
Deansleigh Road
Bournemouth BH7 7DU
020 3664 6755
enquiries@torandco.com
www.torandco.com