





From: John Hall [REDACTED]
Sent: 01 August 2019 14:52
To: Richard Castro-Parker <Richard.Castro-Parker@arun.gov.uk>
Subject: RE: F/5/19/PL

Hello Richard,

The Surface Water Drainage Condition stated in your email below is agreed.

Many thanks, John.

John Hall MBA MCIOrt
John Hall Consulting Ltd.



www.johnhallconsulting.co.uk

From: Richard Castro-Parker <Richard.Castro-Parker@arun.gov.uk>
Sent: 01 August 2019 14:35
To: John Hall [REDACTED]
Subject: FW: F/5/19/PL

Dear Mr Hall,

As discussed on the telephone moments ago, please see the drainage condition below. Do you agree to this? Please reply to this email with your response.

Yours sincerely

Richard Castro-Parker
Senior Planning Officer (Contract)
Arun District Council

From: Juan Baeza
Sent: 01 August 2019 14:32
To: Richard Castro-Parker <Richard.Castro-Parker@arun.gov.uk>
Subject: FW: F/5/19/PL

Juan Baeza Area Team Leader – Planning Department, Arun District Council | Location: First Floor, Arun Civic Centre, Maltravers Road, Littlehampton, BN17 5LF

Internal: 37765 | External: +44 (0) 1903 737765 | E-mail: juan.baeza@arun.gov.uk

Visit Arun's web site at www.arun.gov.uk



Save the environment - think before you print.

From: Laura Gibbons
Sent: 01 August 2019 14:32
To: Juan Baeza <Juan.Baeza@arun.gov.uk>
Subject: F/5/19/PL

Engineers Comments Regarding Surface Water Drainage

If you are minded to approve this application please apply the following condition to ensure the development is adequately drained and does not increase flood risk elsewhere.

PCENG D2

"Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity."

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And please include the accompanying informative:

INFORM D

"Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The percolation tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year event plus 40% on stored volumes, as an allowance for climate change. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest winter groundwater table in support of the design. The applicant is advised to discuss the extent of groundwater monitoring with the Council's Engineers.

Supplementary guidance notes regarding surface water drainage are located here

<https://www.arun.gov.uk/surfacewater> on Arun District Councils website. A surface water drainage checklist is available here <https://www.arun.gov.uk/drainagechecklist> on Arun District Councils website, this should be submitted with a Discharge of Conditions Application."

Regards,

Laura Gibbons, MEng, GMICE
Engineer (Drainage & Coastal)

Laura Gibbons | Engineer (Drainage & Coastal), Engineering Services, Arun District Council | Location: First Floor, Arun Civic Centre, Maltravers Road, Littlehampton, BN17 5LF

Internal: 37818 | External: +44 (0) 1903 737818 | Fax: +44 (0) 1903 716018 | E-mail: laura.gibbons@arun.gov.uk

Arun is Working in Partnership with Chichester District Council

Visit Arun's web site at <http://www.arun.gov.uk/> and www.chichester.gov.uk



Save the environment - think before you print.

<http://www.arun.gov.uk>

DX 57406 Littlehampton

You can view Arun District Council's Privacy Policy from <https://www.arun.gov.uk/privacy-policy>

Important Notice This e-mail is intended exclusively for the addressee and may contain information that is confidential and/or privileged. If you are not the intended recipient (or authorised to receive it for the addressee), please notify the sender and delete the e-mail immediately; using, copying, or disclosing it to anyone else, is strictly prohibited and may be unlawful. Any views, opinions or options presented are solely those of the author and do not necessarily represent those of Arun District Council. The information in this e-mail may be subject to public disclosure under the Freedom of Information Act 2000, therefore we cannot guarantee that we will not provide the whole or part of this e-mail to a third party. The Council reserves the right to monitor e-mails in accordance with relevant legislation. Whilst outgoing e-mails are checked for viruses, we cannot guarantee this e-mail is virus-free or has not been intercepted or changed and we do not accept liability for any damage caused. Any reference to "e-mail" in this disclaimer includes any attachments.
