




From: Sarah Burrow <Sarah.Burrow@arun.gov.uk>
Sent: 16 June 2021 16:12
To: Planning.Responses <Planning.Responses@arun.gov.uk>
Cc: Anita Gardner <Anita.Gardner@arun.gov.uk>
Subject: RE: Planning Consultation on: F/5/21/PL

Engineers Comments Regarding Surface Water Drainage

The applicant has considered surface water drainage of the proposed development and supplied a Surface Water Drainage Summary, Calculations and FRA. They propose to discharge surface water to the watercourse at the northern boundary as high groundwater (up to 0.29mbgl) precludes infiltration as a means of disposal. We agree with this general approach.

We are pleased to note that appropriate buffers to the watercourses are applied to the Site Layout. However, we question how the attenuation tanks will be positioned above peak groundwater levels (as stated on drawing D1906-500) without ground raising. It is assumed that the storage features on the site (the geocellular tank and permeable paving sub-bases) will be lined with an impermeable liner and we would expect to see calculations to show that the effect of buoyancy from the high groundwater has been counteracted.

A discharge rate of 4l/s is being proposed, yet greenfield run-off rate calculations have not been supplied. **Please contact this department as soon as possible and in advance of making an Ordinary Watercourse Land Drainage Consent application and a Discharge of Conditions Application to agree an appropriate discharge rate for the site.** The Ordinary Watercourse Land Drainage Consent application should be made in advance of a Discharge of Conditions application as the consent will need to be supplied.

Further information on the level of detail that is required to avoid pre-commencement conditions, and indeed to discharge those conditions can be found on our Drainage Checklist, available at www.arun.gov.uk/surfacewater. (This includes construction detail drawings).

No part of the Drainage Strategy should be assumed to be approved or listed as an approved document should you be minded to grant planning permission. If you are minded to approve the application please apply the following conditions to ensure that the development is adequately drained and does not increase flood risk elsewhere.

PCENG D2

"Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS

Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity."

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the accompanying informative:

INFORMD

"Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The percolation tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm event plus 40% on stored volumes (allowance for climate change) between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year storm event plus 40% on stored volumes. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest winter groundwater table in support of the design. The applicant is advised to discuss the extent of groundwater monitoring with the Council's Engineers.

Supplementary guidance notes regarding surface water drainage are located here Council on Arun District Councils website. A surface water drainage checklist is available on Arun District Councils website, this should be submitted with a Discharge of Conditions Application."

PCENG D3

"The development shall not proceed until details have been submitted to and approved in writing by the Local Planning Authority for any proposals: to discharge flows to watercourses; or for the culverting, diversion, infilling or obstruction of any watercourse on or adjacent to the site. Any discharge to a watercourse must be at a rate no greater than the pre-development run-off values and in accordance with current policies. No construction is permitted, which will restrict current and future landowners from undertaking their riparian maintenance responsibilities in respect to any watercourse or culvert on or adjacent to the site. "

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W DM1, W DM2 and W DM3 of the Arun Local Plan. And to ensure that the duties and responsibilities, as required under the Land Drainage Act 1991, and amended by the Flood and Water Management Act 2010, can be fulfilled without additional impediment following the development completion. It is considered necessary for this to be a pre-commencement condition to protect existing watercourses prior to the construction commencing.

And the accompanying informative:

INFORMD2

"Under Section 23 of the Land Drainage Act 1991 Land Drainage Consent must be sought from the Lead Local Flood Authority (West Sussex County Council), or its agent (Arun District Council land.drainage@arun.gov.uk), prior to starting any works (temporary or permanent) that affect the flow of water in an ordinary watercourse. Such works may include culverting, channel diversion, discharge of flows, connections, headwalls and the installation of trash screens.

The development layout must take account of any existing watercourses (open or culverted) to ensure that future access for maintenance is not restricted. No development is permitted within 3m of the bank of an ordinary watercourse, or 3m of a culverted ordinary watercourse."

PCENG D4

“Development shall not commence until full details of the maintenance and management of the surface water drainage system is set out in a site-specific maintenance manual and submitted to, and approved in writing, by the Local Planning Authority. The manual is to include details of financial management and arrangements for the replacement of major components at the end of the manufacturer's recommended design life. Upon completed construction of the surface water drainage system, the owner or management company shall strictly adhere to and implement the recommendations contained within the manual.”

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W DM1, W DM2 and W DM3 of the Arun Local Plan. It is considered necessary for this to be a pre-commencement condition to ensure that the future maintenance and funding arrangements for the surface water disposal scheme are agreed before construction commences.

ENGDI

“Immediately following implementation of the approved surface water drainage system and prior to occupation of any part of the development, the developer/applicant shall provide the local planning authority with as-built drawings of the implemented scheme together with a completion report prepared by an independent engineer that confirms that the scheme was built in accordance with the approved drawing/s and is fit for purpose. The scheme shall thereafter be maintained in perpetuity.”

Reason : To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan.

Kind Regards,

Sarah Burrow
Engineering Assistant, Engineering Services

T: 01903 737815

E: sarah.burrow@arun.gov.uk

Current working pattern: Monday 8am-2.30pm, Tuesday 8am-5.30pm, Wednesday 8am-5pm, Thursday 8am-5.30pm, Friday 8am-11.30am.

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk

Sign up to our newsletter [here](#)



From: Planning.Responses <Planning.Responses@arun.gov.uk>

Sent: 29 April 2021 08:34

To: Land Drainage <Land.Drainage@arun.gov.uk>

Subject: Planning Consultation on: F/5/21/PL

To: **Engineers (Drainage)**

NOTIFICATION FROM ARUN DISTRICT COUNCIL

Town & Country Planning Act 1990 (as amended)

Town and Country Planning (Development Management Procedure) (England) Order 2015

Planning Permission

Application No: F/5/21/PL
Registered: 29th April 2021
Site Address: Land rear of Paynters Croft Burndell Road Yapton BN18 0HR
Grid Reference: 498595 102723
Description of Works: Erection of 23 No. dwellings. This application is a Departure from the Development Plan & is in CIL Zone 3 & is CIL Liable as new dwellings.

The Council have received the above application.

[Click here to view the application details](#)

This application has been identified as CIL Liable. Therefore please be aware that, in accordance with Appendix 2 of the Arun CIL Charging Schedule, your consultation response should only include requests for Section 106 for onsite mitigation, Pagham Harbour Management Contributions (if applicable) or Affordable Housing. "Off" Site mitigation measures directly related to this development should be dealt with by condition if possible to ensure the scaling back of Section 106 if possible. CIL contributions will be used for "off" site infrastructure mitigation schemes. Therefore if this proposal triggers the need for "off" site mitigation, please ensure that you engage in the CIL Infrastructure List Consultation process upon receipt of a consultation letter.

Should you have any comments to make, these should be sent by replying to this email by 4th June 2021 . You can also monitor the progress of this application through the Council web site:

www.arun.gov.uk/planning.

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website <https://www.arun.gov.uk/development-plan> as can the the leaflet how to respond to planning applications <https://www.arun.gov.uk/planning-application-comments> which deals with material planning considerations.

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: <https://www.planningportal.co.uk/info/200207/appeals> but they will protect personal details.

In the absence of a reply within the period stated, I shall assume that you have no observations to make

Yours sincerely

Mrs A Gardner

Planning Officer- Arun District Council

Telephone: 01903 737529

Email: Anita.Gardner@arun.gov.uk