Proposed new house

At

Plot 2 – 69 Coastal Road, East Preston

Schedule of external Materials

Roof

Flat roof to be finished with single ply polymeric membrane - Alwitra Evalon V- RAL 7015 (Slate Grey)

Walls

Walls to be rendered with through colour render - Weber Pral M- Chalk

Wall projecting from front elevation adjacent to main entrance to be clad with stacked slate cladding - Norstone Rock Panel- Charcoal

Doors and windows

Doors and windows to be by Velfac with powder coated aluminium external finish, coulour to be RAL 7016 (Anthracite)

ARUN DISTRICT COUNCIL K/16/14/DOC