

Balcony Details

Q-Railing system 1.1m high – further height restricted due to high winds and micro-climate.
Pilkington Clear safety glass to north and south. Pilkington Opaque safety glass to east and west elevations.

Q-Railing

Designed for:	Light and medium use
Use:	Indoor and outdoor
Suitable for:	Top, in-floor and fascia mounting
Applications:	Stairs and balustrades
Material:	Brushed or mill-finished aluminium
Infill:	Glass
Glass thickness:	12 to 21.52 mm
Top finish:	Cap rail, U-profile or edge protection
Features:	■ Symmetrical top-mount base shoe that also allows for inverse mounting ■ Minimal use of anchors in base shoe installation ■ Easy base shoe installation with a choice of fixing methods (hexagon bolts, mechanical anchors or stud anchors, and cost-effective anchor options) ■ Optional aluminium shoe shims ■ available for levelling uneven surfaces Incredibly simple glass mounting with ground-breaking Q-disc System and Q-disc tool Resists line loads of up to 0.74 kN/m