

BOUNDARY TREATMENTS

A. Close Board Fencing
1500mm high with 300mm trellis above

B. Stained Close Board Gate
1800mm high

HARD & SOFT LANDSCAPING

1. Concrete Setts.

Marshalls Driveline Priora permeable block paving
Colour Brindle [BRI]
200 x 100 x 60, laid herringbone pattern.

2. Natural Stone Paving

Cotswold stone chippings to provide permable surface on
100mm Type 1 sub base

3. Turf .

Turf to be to BS 3969. Turf to be laid as described in BS 4428 section 6.
Finished turf levels to be 20mm above adjacent hard surfaces.
Supply and lay turf to prepared surfaces of ground including, watering,
weeding and initial cutting when established.

4. Planting.

3No. Choisya Ternata Sundance (Evergreen, drought resistant, shrubs)
1.5 metre spread and 1.5metre high planted within border and dressed
with bark chippings to retain moisture.

- Covered storage for 3 Bicycles
provided by 1800 x 1200 mm garden shed.
- Drying Line [minimum 6 metres]
Supplier: Brabantia 25 metre line
Adjacent to hardstanding.
- Dedicated waste containers [140 litres]
2 No. labelled bins as detailed in compliance notes. On hardstanding.
Combined internal recycling bin [30 litres]
located in kitchen. Waste sorted after collection.
- Water Butt
Sankey 210 litre water butt on stand with
overflow to soakaway
- Sankey Home Composter
220 Litre capacity

A. 0115 gm Additional notation regarding soft landscaping added.

Rev Date Amend Revision

Gerald Moore RIBA. Chartered Architect

1 Exmoor Crescent Worthing West Sussex BN13 2PL

Tel: 01903 609607 Mobile: 07793 00 44 62

www.geraldmooreriba.co.uk e-mail: contact@geraldmooreriba.co.uk

Client: MISS L. CLARKE

Project: LAND REAR OF 27-29b SURREY STREET
LITTLEHAMPTON BN17 5BD

Drawing: EXTERNAL WORKS PLAN

Drg No: 1227/14/EW/01A

Scales: 1:100 Date: JULY 2014

Drawn: gm Drwg Size: A2

This drawing is the copyright of Gerald Moore RIBA. The contractor should check all dimensions on site.
No dimensions are to be scaled from this drawing except for planning purposes. It is the contractor's responsibility
to ensure that all works are in compliance with the current statutory requirements.