© Mayer Brown Limited Copyright. The drawings, information and data recorded in this document ("the Information") is the property of Mayer Brown. This document and the information are solely for the use of the authorised recipient and this document may not be used, copied or reproduced in whole or part for any purposes other than which it was supplied by Mayer Brown. Mayer Brown makes no representation, undertakes no duty and accepts no responsibilities to any third party who may use or rely upon this document or the information.

A0 ORIGINAL

© Crown copyright, all rights reserved. 2017. Licence number 100021265.

KEY

- EXISTING KERB LINE
- PROPOSED KERB/EDGING LINE
- PROPOSED DROPPED KERB
- PROPOSED ROAD MARKING
- PROPOSED BUFF COLOURED TACTILE PAVING
- PROPOSED CORDUROY HAZARD WARNING PAVING
- LIMIT OF WORKS


Future continuation of Road Two

Future continuation of the Main Avenue

Future continuation of Road Six

VIEWPORT 5

FOR CONTINUATION REFER TO DRAWING A/PHLITTLE-INT.1/XX-1



DB32 Fire Appliance

Overall Length	8.680m
Overall Width	2.180m
Overall Body Height	3.452m
Min Body Ground Clearance	0.137m
Max Track Width	2.121m
Lock to lock time	6.00s
Kerb to Kerb Turning Radius	7.910m

NOTES:

1. Based on topographic survey by WYG drawing numbered GGL/A044029/LAY/01.
2. Site layout taken from PHTV drawing numbered 543_PL_SITE LAYOUT_REV B.

PRELIMINARY
NOT FOR CONSTRUCTION

rev.	amendment	checked	date
P2	Drawing amended following updated site layout received from PHTV dated 08/09/2017. (OJN)	AB	11/09/2017
P1	Initial issue. (OJN)	AB	05/09/2017

mayer brown

Mayer Brown Limited
Lion House Oriental Road Woking Surrey GU22 8AR
Telephone 01483 750 508 Fax 01483 750 427
wokingoffice@mayerbrown.co.uk www.mayerbrown.co.uk

client
PERSIMMON HOMES THAMES VALLEY

project
NORTH LITTLEHAMPTON PHASE 2
PARCEL C1 AND PART PARCELS, B2, B4 & C2

scale	1:250	drawn by	OJN	checked by	AB
date	SEPTEMBER 2017	cad file	MASTER.DWG		

title
ANTICIPATED SWEPT PATH OF A FIRE TENDER ACCESSING THE SITE (2 of 2)

drawing number
A/PHLITTLE-INT.1/TK-4

rev.
P2