

REASONS FOR PROPOSED TREE WORK

T1 Lime adjacent to the drive entrance with East Street:

- Prune to previous pollard knuckles
- Lateral prune to union the 2 x pollard knuckles that overhang the adjacent boundary wall

- Current height 13.5m
- Finished height 9.0m

	<u>Current branch length</u>	<u>Finished branch length</u>
North	6.5m	3.5m
East	6.5m	4.0m
South	5.0m	3.0m
West	5.0m	3.0m

- Remove all growth from along the stem and from within the crown

T2 Sycamore adjacent to the entrance to the Flintstone Centre:

- Prune the new growth back to the previous topping points

- Current height 15.0m
- Finished height 11.0m

	<u>Current branch length</u>	<u>Finished branch length</u>
North	4.0m	2.5m
East	5.0m	2.5m
South	6.5m	5.5m
West	6.0m	4.0m

- Remove any dead stubs from the truncated ends

T3 & T4 Holm Oak along the boundary wall with East Street:

- Prune to previous pollard knuckles – both trees are being treated as one crown form due to their growth habit

- Current height 15.0m
- Finished height 10.0m

	<u>Current branch length</u>	<u>Finished branch length</u>
North	6.5m	4.5m
East	6.5m	3.5m
South	/m	/m
West	6.0m	3.0m

T1, T3 and T4 have been pruned and managed as pollards, the specification is seen as a continuation of this method of management.

T2 has been topped and the management of the resultant growth will mirror that of a pollard; over time pollard knuckles will develop and match those of the other trees.