

TEST REPORT :
DETERMINATION OF THE GEOMETRICAL PROPERTIES OF AGGREGATE

BSEN 933-11:2009 Classification Test For The Constituents Of Coarse Recycled Aggregate

REPORT No.:	5013327 / 368534.10.1.3	CLIENT:	ERITH CONTRACTORS LTD
SAMPLE No.:	583259	ADDRESS:	Erith House
CLIENT REF:	5013327	SITE:	SGN Littlehampton Holder Station
DATE SAMPLED:	15/09/2025	SUPPLIER:	EURO GREEN ENVIRONMENT
SAMPLED BY:	Kinter Zvokunzwa	MATERIAL:	Brown slightly silty slightly sandy clayey GRAVEL
DATE RECEIVED:	17/09/2025	LOCATION:	Stockpile
DATE TEST COMPLETED:	17/10/2025	ACCEPT STD:	Contract Specification
TESTED BY:	BV	SAMPLING CERT.:	Available
DRYING TEMPERATURE:	40±5°C	SAMPLING PLAN:	CTS Procedure

TEST RESULT: Test Location; Heathrow Laboratory

	CONSTITUENT	FOUND PROPORTION	SPECIFICATION (%)
Rc	Concrete, concrete products & concrete masonry units.	35 %	Not Specified
Ru	Unbound aggregate, natural stone & Hydraulically bound aggregate. (% of CHALK found within Ru)	47 % 1.4 %	Not Specified
Rb	Clay masonry units (ie.bricks & tiles), calcium silicate masonry units & aerated non-floating concrete	15 %	Not Specified
Ra	Bituminous Material	1 %	50
Rg	Glass	0.1 %	Not Specified
X	Other: Cohesive (ie clay & soil), gypsum plaster, miscellaneous - metals (ferrous & non ferrous), non-floating wood, plastic & rubber.	2.8 %	Outside Limits 1.0
FL	Floating Particles	7.2 cm ³ /kg	Not Specified

REMARKS:

Test results reported relate only to the items tested.
This report shall not be reproduced except in full without approval of the laboratory.

For and on behalf of CTS

Shah Alam Acting Laboratory Manager
Approved signatory
17-Oct-25



4161

Page 1 of 1

Report Format: L/Rep A16/rev.2

Opinions and interpretations expressed herein are outside the scope of UKAS Accreditation
The laboratory does not apply a conformity statement to test reports as standard, unless specifically requested by the customer
End of Report