

Remove existing fixed window bench seat and examine the exposed floor covering. If needed, extend the existing acoustic floor treatment into this area and seal at the perimeter.

Remove existing plasterboard dry lining and battens and replace with 15 mm 'Gyproc SoundBloc' plasterboard on resilient bars on treated battens with minimum 25 mm 'Celotex' insulation inbetween.

SVP.

Extract fan.

DH

KITCHENETTE

SHOWER

BEDROOM

LIVING AREA

FD30

DS

LOBBY

FD30S

FLAT 3

DS

LANDING

EL

FLAT 4

CPID

LOBBY

FD30S

DS

STUDIO FLAT

DH

Reduce window width to suit room layout.

Manual call point.

Smoke detector head.

Heat detector head.

Emergency lighting.


Remove existing plasterboard dry lining insulation and battens and replace with 15 mm 'Gyproc SoundBloc' plasterboard on resilient bars fixed to the existing 225 mm solid wall. Provide dense mineral fibre insulation between the studs where the old doorway has been filled in.

Remove existing plasterboard dry lining, expanded polystyrene insulation and battens and replace with 15 mm 'Gyproc SoundBloc' plasterboard on resilient bars fixed to treated battens with minimum 25 mm 'Celotex' insulation inbetween.

Means of escape window.

To the common area walls, remove existing plasterboard on latins and plater and replace with 15 mm 'Gyproc SoundBloc' plasterboard on resilient bars fixed to the existing stud wall with minimum 50 mm dense mineral fibre batts between studs.

## PROPOSED FIRST FLOOR PLAN



SUSSEX BUILDING CONSULTANCY LIMITED

4 ST AUGUSTINE ROAD, LITTLEHAMPTON,  
WEST SUSSEX.

SCALE - 1/50 REV - D DATE - 26/04/2019

partner

LABC

3 NORTHGATE ROAD  
BOGNOR REGIS  
PO21 3LZ  
TEL/FAX - (01243) 861379