

landscaping 747/104

Fencing 1.800 high feather edge fencing fixed to three levels of arris rails and gravel boards, centre stump. Pressure treated fence posts. Posts 600 into ground and surrounded by concrete

Replace East boundary fence in correct position with 1.800 high boarded fencing
Fencing west and south to be replaced where necessary with 1800 boarded fencing
Rear separating fence 1.000 high and 1.800 next to patio

Patio Marshalls 400 x 400 x 38 Argent permeable paving colour dark paving slabs,
Joints filled with kiln dried sand
50 mm compacted sand on geotextile on 200mm hardcore

Side of houses 900 wide concrete path with 100 gravel next to house

1,800 fences to sides and forming bin store. Lockable timber ledged and braced gates.

Choisya shrubs in front of fence forming bin store and front fence.

Edging restraint with concrete footing and haunching.

Minimum of 2 x 75mm compacted Type 1 MOT aggregate

North fence to road frontage to be 1.000 high

Front of house Mulhonia removed to allow entrance to car parking and replaced

