

REASONS FOR PROPOSED TREE WORK

T1 English oak in rear garden:

- Reduce apical and lateral spread by 1.5m

- Current height 9.5m
- Finished height 8.0m

	<u>Current branch length</u>	<u>Finished branch length</u>
North	6.0m	4.5m
East	5.0m	4.5m
South	4.5m	4.5m
West	5.5m	4.5m

- Remove deadwood over 25mm in diameter

The tree is beginning to get too big for its position with branches extending over the neighbouring properties.

The specification is intended to produce a smaller tree whilst retaining its overall aesthetic appeal.