KENNEY DRIVE ROAD TWO (20MPH)

Approved 126 units
RM Scheme

Approved 126 units
RM Scheme

LEAP 400m²

Five Stones Nursery

KEY:

Proposed Infrastructure Drainage:

Detail provided by Mayer Brown (current at time of issue but must be checked against their latest revisions). All Infrastructure road drainage is to be constructed from Mayer Brown design detail, with any discrepancies brought to MJA's attention.

Proposed Private Drainage:

Foul drain

Storm drain

Rodding eye

Yard gully

Linear drainage channel — LINEAR DRAINAGE CHANNEL

ACO or similar approved. Connection Invert Level dependent on manufacturers specifications.

All private inspection chambers shall be polypropylene non-access chambers in accordance with The Building Regulations, Part H.

Chamber sizes:
Depth to invert <0.6m DN300
Depth to invert >0.6m DN475

Invert levels shown thus: F10.00 S10.00

Finished floor levels shown thus: FFL 10.000

Primary Access ▽ Secondary Access

Proposed 2.8m High Acoustic Fence Location
- details to be provided by Persimmon Homes

REV. No.	DATE	DESCRIPTION	INITIALS

Client: Persimmon Homes (Thames Valley)

Project: Phase 2 Littlehampton

Title: Area in Abeyance – Drainage Plan

Scale: 1:250 @A2 | Date: July 2020 | Drawing No.: 5691:05PL | Rev:

Checked: RC | Drawn: AT