




- LEGEND - WALL FINISHES -
- JBSTOCK Arundel Yellow Multi Brick (Buff) (B1)
 - FORTEBBA Milton Buff Brick (B3)
 - AAB BR48 Buff Brick (B2)
 - Detail Brick 3 No. projecting Dentil course; BrickWorks - Rotheray Smooth Brick (B4)
 - Detail Brick Projecting string course to weatherboard edge. to be as main facing brick type.
 - Detail Brick Projecting string course and Brick Feature Detail (see note below). to be as main facing brick type.
 - RECONSTITUTED STONE Stone Detailing / Stone Banding / Stone Coping - Portland Stone colour (S)
 - RENDER KRender Antique White (R)
 - HARDIE PLANK Weatherboard Cladding Cobble Stone (WB1)
 - HARDIE PLANK Weatherboard Cladding Timber Bark (WB2)
 - RENDER KRender Antique White (R)

PLEASE NOTE:
All Rainwater goods to be Black uPVC with half round gutters and round downpipes.
All Windows are to be recessed within the external brickwork by 40mm and All fenestration, Front Doors and associated Garage Doors to be uPVC Slate Grey (RAL 7015) smooth.
All Fascias, Soffits & Bargeboards to be uPVC Slate Grey (RAL 7015)
Apartment Block balcony glazing to be 10mm Opaque toughened glass with steel handrails / frame.
Brick pattern / Feature Brick above window head height within recessed balcony projections on Apartment Blocks to be Flemish bond with alternate snap headers and whole brick projecting stretchers - Refer to Elevations.



Rev		Date
-		-
 PERSIMMON Together, we make a home		
Persimmon Homes Thames Valley Persimmon House, Knoll Road, Camberley, Surrey GU15 3TQ Tel: 01276 808080		
Site:	Date:	
Phase 2B Littlehampton	April 2021	
Scale:	1:500 @ A1	
Org No:	545_PL_AP2_106	
Drawing Title:		
External Wall Finishes Plan		
Drawing Status:	Drawn:	Checked:
SUBMITTED	AT	ME
Rev:	-	