

From: Harris, Aimee [REDACTED]
Sent: 23 February 2022 12:59
To: Michael Eastham <Michael.Eastham@arun.gov.uk>
Subject: LU/206/21/RES - PHASE 5, HAMPTON PARK

CAUTION: This email originated from outside of the organisation. You should take extra care when clicking links or opening attachments - if you are unsure the content is safe contact the IT Helpdesk before clicking or opening.

Hi Michael

Please find attached noise comments in response to the Environment Health Officer's comments in relation to Phase 5.

Kind regards

Aimee

Aimee Harris
Planner

Persimmon Homes Thames Valley
Persimmon House
Knoll Road
Camberley
GU15 3TQ

From: Carol Reynolds <Carol.Reynolds@arun.gov.uk>
Sent: 17 November 2021 15:31
To: Michael Eastham <Michael.Eastham@arun.gov.uk>
Subject: FW: LU/206/21/RES - PHASE 5, HAMPTON PARK
Importance: High

Dear Michael,

Environmental Health : I refer to the attached Tetra Tech Noise Assessment, 784-B028030, April 2021. The figures provided in Tables B1&2, Appendix B show that BS:8233 guidelines cannot be achieved in habitable rooms with windows open. The ProPG states that design layout should be optimised so that habitable rooms are oriented away from sources of adverse noise. I have looked at the layout of sample house types along the road which demonstrate that habitable rooms, including bedrooms in roofs, could be reorientated to face away from the predominant source of noise ie the road. Arun Planning Department may of course consider this unsatisfactory, due to change that this would bring to the 'street scene.'

In this case, mechanical means of acoustically treated artificial ventilation should be provided to all adversely effected houses and flats, so that future occupants will have the option of controlling thermal comfort with the windows closed. Such a system should be based on based on MEV3 or 4 as detailed in the Building Regulations, Approved Document F. Whereas the report mentions that mechanical ventilation may be required, this is excluded from Fig 5, Glazing and Ventilation Strategy which only details proposed glazing and passive ventilation.

Please could the applicant use acoustic archives to assess the number of times and degree to which the criterion of not more than 10 to 15 events greater than 45dBL_{a,f,max} is likely to be exceeded in bedrooms during night-time hours in accordance with the ProPG and BS8233 guidelines. Arun EH aim for not more than 12 events of greater than 45DBLA, f, max, 5 mins, per night inside bedrooms. Closer definition may be required.

I understand that some modification of house types is intended along the link road, for example possibly plots 102, 103 and 106. Any updated report will of course, need to take this into consideration.

I would be obliged if you would explain why a correction of -3.7dB has been made to the night-time noise levels.

Gardens - No comment. Satisfactory.

Balconies - No comment. Satisfactory

Other areas of external amenity and heat source pumps

*I understand that this report deals exclusively with the effect of the spine/link road on directly adjacent proposed residential units. Please note that an acoustic report will also be required in the case of the LAP and LEAP external amenity areas, which embrace the southern section of the spine road (shown on the front page of this report).

*This department will require details to ensure that any air/other source heat pump if intended to be installed, will not cause noise to the detriment.

* The pumping station has already been dealt with.

The granting of this planning permission does not in any way indemnify against statutory nuisance action being taken should substantiated complaints within the remit of the Environmental Protection Act 1990 be received.

Kind regards
Carol

Carol Reynolds
Senior Environmental Health Officer
Environmental Health Department



T: 01903 737678

E: carol.reynolds@arun.gov.uk

Please note my normal working days are Tuesday to Friday

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk



Sign up to our newsletter [here](#)

Business Support during Coronavirus click [here](#)

Carol Reynolds
Senior Environmental Health Officer
Environmental Health Department



T: 01903 737678

E: carol.reynolds@arun.gov.uk

Please note my normal working days are Tuesday to Friday

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk



Sign up to our newsletter [here](#)

Business Support during Coronavirus click [here](#)

From: Michael Eastham <Michael.Eastham@arun.gov.uk>

Sent: 21 October 2021 16:16

To: Carol Reynolds <Carol.Reynolds@arun.gov.uk>

Subject: RE: LU/206/21/RES - PHASE 5, HAMPTON PARK

Importance: High

Dear Carol,

Please find attached a copy of the **Noise Assessment** for **LU/206/21/RES**.

I look forward to receiving your consultation response.

Kind regards,

Michael

From: Carol Reynolds <Carol.Reynolds@arun.gov.uk>

Sent: 21 October 2021 16:05

To: Michael Eastham <Michael.Eastham@arun.gov.uk>

Subject: FW: LU/206/21/RES

Dear Michael,

I can only apologise in that Chima had received this application which was only passed to me on 12th October.

Please could you send me a colour copy of the noise report and I will make our return asap.

I note that the Energy & Sustainability Statement includes installation of gas boilers. Will this need to change given the Government's recent decision to phase their out use//favour air/ground source heat pumps? Such an alternative would need to be subjected to a noise assessment.

Kind regards

Carol

Carol Reynolds

Senior Environmental Health Officer

Environmental Health Department



T: 01903 737678

E: carol.reynolds@arun.gov.uk

Please note my normal working days are Tuesday to Friday

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF

www.arun.gov.uk



Sign up to our newsletter [here](#)

Business Support during Coronavirus click [here](#)

From: Chima Umunnakwe <Chima.Umunnakwe@arun.gov.uk>

Sent: 07 October 2021 15:29

To: Carol Reynolds <Carol.Reynolds@arun.gov.uk>

Subject: LU/206/21/RES

Hi Carol,

See the above planning reference for the case we spoke about. I have also changed it over on Tascomi.

Regards

Chima Umunnakwe
Environmental Protection Officer
Technical Services



T: 01903 737336

E: chima.umunnakwe@arun.gov.uk

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk

Due to the current pandemic, work is being prioritised according to public safety risks and you may not receive an immediate response to your email. Wherever possible we will endeavour to respond within 7 working days.

The Environmental Health Team in particular are focused on supporting COVID-19 compliance, and other services may be limited or delayed. Further details of our current service levels can be found at: <https://www.arun.gov.uk/service-status>

If you are making contact for advice or to register a new request for service, including enquiries about COVID-19, food safety, noise or pollution, you can register these directly on-line at <https://eh.arun.gov.uk/>



<http://www.arun.gov.uk>


DX 57406 Littlehampton

You can view Arun District Council's Privacy Policy from <https://www.arun.gov.uk/privacy-policy>


Important Notice This e-mail is intended exclusively for the addressee and may contain information that is confidential and/or privileged. If you are not the intended recipient (or authorised to receive it for the addressee), please notify the sender and delete the e-mail immediately; using, copying, or

disclosing it to anyone else, is strictly prohibited and may be unlawful. Any views, opinions or options presented are solely those of the author and do not necessarily represent those of Arun District Council. The information in this e-mail may be subject to public disclosure under the Freedom of Information Act 2000, therefore we cannot guarantee that we will not provide the whole or part of this e-mail to a third party. The Council reserves the right to monitor e-mails in accordance with relevant legislation. Whilst outgoing e-mails are checked for viruses, we cannot guarantee this e-mail is virus-free or has not been intercepted or changed and we do not accept liability for any damage caused. Any reference to "e-mail" in this disclaimer includes any attachments.

We are proud to be an official partner of Team GB.



Persimmon Homes is proud to support local communities. Every year our Community Champions scheme donates £750,000 to local groups and our Building Futures scheme supports young people with donations of over £1 million. [Find out more...](#)



Disclaimer

The information in this email is confidential and may be legally privileged. It is intended solely for the addressee. Access to this email by anyone else is unauthorised. If you are not the intended recipient, any disclosure, copying, distribution or any action taken or omitted to be taken in reliance on it, is prohibited and may be unlawful. If you are not the intended recipient please contact the sender and delete the message.

Our privacy policies for our customers, employees and job applicants are available at <https://www.persimmonhomes.com/corporate/corporate-responsibility/policies>

Persimmon Homes Limited is registered in England number 4108747, Charles Church Developments Limited is registered in England number 1182689 and Space4 Limited is registered in England number 3702606. These companies are wholly owned subsidiaries of Persimmon Plc registered in England number 1818486, the Registered Office of these four companies is Persimmon House, Fulford, York YO19 4FE.

This email has been scanned for viruses and malware, and may have been automatically archived by Mimecast Ltd, an innovator in Software as a Service (SaaS) for business. Providing a **safer** and **more useful** place for your human generated data. Specializing in; Security, archiving and compliance. To find out more [Click Here](#).

As part of its obligations under Part 3, Criminal Finances Act 2017, Persimmon operates a zero tolerance approach to the criminal facilitation of tax evasion.

<https://www.persimmonhomes.com/corporate/media/334191/prevention-of-criminal-facilitation-of-tax-evasion-policy.pdf>

.....
This message contains confidential information and is intended only for the recipient. If you are not the recipient you should not disseminate, distribute or copy this e-mail. Please notify the sender immediately by e-mail if you have received this e-mail by mistake and delete this e-mail from your system. E-mail transmission cannot be guaranteed to be secure or error-free as information could be intercepted, corrupted, lost, destroyed, arrive late or incomplete, or contain viruses. The sender therefore does not accept liability for any errors or omissions in the contents of this message, which arise as a result of e-mail transmission. If verification is required please request a hard-copy version. Tetra Tech is a trade name of the Tetra Tech Group, for our contracting entity company details please refer to our appointment documentation.
.....

.....
This message contains confidential information and is intended only for the recipient. If you are not the recipient you should not disseminate, distribute or copy this e-mail. Please notify the sender immediately by e-mail if you have received this e-mail by mistake and delete this e-mail from your system. E-mail transmission cannot be

guaranteed to be secure or error-free as information could be intercepted, corrupted, lost, destroyed, arrive late or incomplete, or contain viruses. The sender therefore does not accept liability for any errors or omissions in the contents of this message, which arise as a result of e-mail transmission. If verification is required please request a hard-copy version. Tetra Tech is a trade name of the Tetra Tech Group, for our contracting entity company details please refer to our appointment documentation.

784-B028030

23rd February 2022

Response to comments received from Carol Reynolds, Senior Environmental Health Officer at Arun District Council (ADC) regarding the submitted Noise Assessment by Tetra Tech [ref 784-B028030 dated 28th April 2021] for planning application reference LU/206/21/RES.

Tetra Tech Responses in Blue

ADC Comment 1

The figures provided in Tables B1&2, Appendix B show that BS:8233 guidelines cannot be achieved in habitable rooms with windows open. The ProPG states that design layout should be optimised so that habitable rooms are oriented away from sources of adverse noise. I have looked at the layout of sample house types along the road which demonstrate that habitable rooms, including bedrooms in roofs, could be reorientated to face away from the predominant source of noise ie the road. Arun Planning Department may of course consider this unsatisfactory, due to change that this would bring to the 'street scene.'

In this case, mechanical means of acoustically treated artificial ventilation should be provided to all adversely effected houses and flats, so that future occupants will have the option of controlling thermal comfort with the windows closed. Such a system should be based on based on MEV3 or 4 as detailed in the Building Regulations, Approved Document F. Whereas the report mentions that mechanical ventilation may be required, this is excluded from Fig 5, Glazing and Ventilation Strategy which only details proposed glazing and passive ventilation.

Tetra Tech Response 1

Within Section 5.1 of the noise assessment, a ventilation specification of D_{new} 30dB is outlined within Figure 5.1 for a number of facades across the site. In order to provide more detailed analysis of the type of ventilation required and assess thermal comfort, the Acoustic, Ventilation and Overheating Guide (AVOG) 2020 has been consulted. This provides guidance for acoustic assessments for residential developments, providing clarity on the relationship between acoustics, overheating and appropriate ventilation requirements. With regards to overheating, AVOG states that as overheating is a temporary condition, during this period "occupants may accept a trade-off between acoustic and thermal conditions, given that they have some control over their environment," and that occupants may "be more willing to accept higher short-term noise levels in order to achieve better thermal comfort."

The AVOG document identifies that the desirable internal noise standards within Table 4 of BS 8233:2014 should be achieved when providing adequate ventilation as defined by ADF whole dwelling ventilation, but that it is considered reasonable to allow higher levels of internal ambient noise from transport sources when higher rates of ventilation are required in relation to the overheating condition. Although this assessment is at the reserved matters stage rather than outline as AVOG and ProPG are intended, the guidance has been used to provide further comfort to the council that the ventilation strategy is sufficient from a noise perspective. The AVOG provides guidance to produce an initial site risk assessment of noise from transportation sources which are reproduced in Figure 1 below.

Risk category for Level 1 assessment (Table 5)	Potential Effect without Mitigation	Recommendation for Level 2 assessment
Living room during 07:00 - 23:00 Living room during 23:00 - 07:00 High 65 dB 55 dB Medium 60 dB 50 dB Low 55 dB Negligible 60 dB 45 dB	Increasing risk of adverse effect	Recommended Optional Not required

Note 6 To evaluate the risk category for a dwelling, all three aspects of external noise exposure (i.e. daytime, night-time and individual noise events) should be evaluated. The highest risk category for any of the three aspects applies.

February 2022

Figure 2 AVOG Daytime Risk Contour Plot (Grid Height: 1.5m)



As shown above, the majority of living room spaces and south-facing facades across the site fall within the Negligible to Low-risk category as defined within the AVOG and therefore as shown within Figure 1 the 'use of opening windows as primary means of mitigating overheating is not likely to result in adverse effect.' Additionally, although not required under the AVOG, acoustic trickle vents are to be installed on a number of living room facades as identified within the noise technical report and combined with the option to open windows, dwellings will be suitable for both thermal and acoustic comfort. Facades exposed to the link road fall just within the Medium Risk category in accordance with the AVOG, however given the predicted levels across the site and given a majority of facades are not south-facing, acoustic trickle vents are considered to be a suitable means of ventilation for these facades.

Figure 3 AVOG Night-time Risk Contour Plot (Grid Height: 4.0m)



As shown above, nearly all bedroom spaces and south facing facades across the site fall within the Negligible to Low risk categories in accordance with the AVOG and therefore as detailed within Figure 1, the 'use of opening windows as primary means of mitigating overheating is not likely to result in adverse effect.' Additionally, although not required under the AVOG, acoustic trickle vents are to be installed on a number of living room facades as identified within the noise technical report and combined with the option to open windows, dwellings will be suitable for both thermal and acoustic comfort. Facades exposed to the link road fall just within the Medium Risk category in accordance with the AVOG, however given the predicted levels across the site and given a majority of facades are not south-facing, acoustic trickle vents are considered to be a suitable means of ventilation for these facades.

An example of acoustic trickle vents which achieve the minimum specification of D_{new} 30dB are Titon's SF Xtra Sound Attenuator Vent where details are presented in Appendix A.

The ventilation strategy outlined here is considered to meet the requirements of BS 8233, and the ventilation requirements outlined in the AVOG.

ADC Comment 2

Please could the applicant use acoustic archives to assess the number of times and degree to which the criterion of not more than 10 to 15 events greater than 45dBL_{A,f,max} is likely to be exceeded in bedrooms during night-time hours in accordance with the ProPG and BS8233 guidelines. Arun EH aim for not more than 12 events of greater than 45dBL_{A, f, max}, 5 mins, per night inside bedrooms. Closer definition may be required.

Tetra Tech Response 2

Given the road is proposed as part of the development, measured levels were not able to be undertaken. As detailed within the noise technical report, noise levels have been calculated from road traffic data provided for the link road and as such analysis of historic L_{Amax} events is not possible. However, it is considered that the mitigation measures outlined within the noise report for the L_{Aeq} scenario would address the majority of peak (L_{Amax}) noise levels from road traffic noise excluding 12 events per night inside bedrooms.

ADC Comment 3

I understand that some modification of house types is intended along the link road, for example possibly plots 102, 103 and 106. Any updated report will of course, need to take this into consideration.

Tetra Tech Response 3

Although the overall findings of the submitted noise assessment are considered unlikely to change significantly, an updated assessment could be undertaken to account for further to changes to the layout.

ADC Comment 4

I would be obliged if you would explain why a correction of -3.7dB has been made to the night-time noise levels.

Tetra Tech Response 4

As the traffic flow data for the link road is provided in 18hr format, a correction has been applied to convert the predicted L_{A10,18hr} traffic flow data to L_{Aeq,8hr} noise levels for the purposes of the night-time assessment. The correction is referenced within 'converting the UK traffic noise index L_{A10,18hr} to EU noise indices for noise mapping' by TRL Limited.

End of Document

Emma Aspinall
Senior Environmental Consultant


Graham Davis
Principal Environmental Consultant

Nigel Mann
Director

Appendix A – Manufacturer's details for Titon SF Xtra Sound Attenuator Vent


SF Xtra Sound Attenuator Vent

Surface mounted noise reducing ventilator



SF Xtra Sound Attenuator Internal

Suitable for:




The SF Xtra Sound Attenuator ventilator is a slot ventilator which provides high levels of sound attenuation compared to similar 'acoustic' products, in a compact size.


The SF Xtra Sound Attenuator can be purchased in a number of combinations based on different sizes of inner (ventilator) and outer (canopy). Combinations can be chosen depending on the sound attenuation requirement and can achieve up to $D_{n,e,w} (C;Ctr) = 44 (-2;-3)$ dB when the vent is open.

The product is a cost effective method of reducing incoming noise in situations where conventional slot ventilators are unable to assist with acoustic issues.

The SF Xtra Sound Attenuator comes fitted with a Titon SF Xtra Ventilator and/or SF Canopy (HF Canopy for 5000EA version) and fits the 2500mm² EA version over the Trimvent® Select, Trimvent® 4000 Hi Lift or Select Xtra slot size.



SF Canopy version



SF Xtra Sound Attenuator Canopy Internal

Features and Benefits

- Cost effective sound attenuating ventilator
- Independently tested by Sound Research Laboratories in accordance with BSEN20140-10:1992, ISO140-10:1991
- 2500mm² EA and 5000mm² EA versions available
- Vent sizes available: V25, V50, V75 and canopy sizes: C25, C50 and C75
- Can provide up to 44 $D_{n,e,w}$ attenuation, depending on combination
- Suitable for use in domestic or non-domestic installations
- Ideal for retrofit applications, over an existing slot
- Available in a range of combinations to suit different acoustic specifications
- Fits over a Trimvent® Select, Trimvent® 4000 Hi Lift or Trimvent® Select Xtra slot size
- Supplied with SF Xtra Ventilator and/or SF Canopy fitted (HF Canopy for 5000EA version)
- High performance gasket combined with compression closing action improves sealing in adverse conditions
- Can be mounted to deflect air upwards or downwards
- For use over a 13mm slot
- Special paint finishes available

Product	Product Code	(L) Length	(W) Width	(P) Projection Closed-Open	Free Area (mm ²)	Slot Detail
SF Xtra 2500EA Vent only	TA5220	425	28	10-24	4207	
SF 418 Canopy only	TA5005	418	23	27	5114	
SF Xtra Sound Attenuator 2500EA Vent 25mm	TA5221	464	35	37-51	3470	
SF Sound Attenuator 2500EA Canopy 25mm	TA5202	464	35	54	3470	
SF Xtra Sound Attenuator 2500EA Vent 50mm	TA5223	464	35	62-76	3470	173.5 20 173.5 13
SF Sound Attenuator 2500EA Canopy 50mm	TA5204	464	35	79	3470	
SF Xtra Sound Attenuator 2500EA Vent 75mm	TA5225	464	35	87-101	3470	
SF Sound Attenuator 2500EA Canopy 75mm	TA5206	464	35	104	3470	
SF Xtra Sound Attenuator 5000EA Vent 75mm	TA5235	523	35	87-101	5517	215 8 215 13
HF Sound Attenuator 5000EA Canopy 75mm	TA5236	523	35	113.5	5517	

Acoustic Ratings

Product	Open	Closed	EA (mm ²)
TA5225 + TA5206 (2500EA)	$D_{n,e,w}(C;Ctr) = 44 (-2; -3)$ dB	$D_{n,e,w}(C;Ctr) = 55 (-1; -5)$ dB	2500
TA5225 + TA5204 (2500EA)	$D_{n,e,w}(C;Ctr) = 42 (-1; -2)$ dB	$D_{n,e,w}(C;Ctr) = 55 (-2; -5)$ dB	2500
TA5225 + TA5005 (2500EA)	$D_{n,e,w}(C;Ctr) = 40 (-1; -2)$ dB	$D_{n,e,w}(C;Ctr) = 53 (-1; -4)$ dB	2500
TA5223 + TA5202 (2500EA)	$D_{n,e,w}(C;Ctr) = 39 (-1; -2)$ dB	$D_{n,e,w}(C;Ctr) = 55 (-2; -5)$ dB	2500
TA5223 + TA5005 (2500EA)	$D_{n,e,w}(C;Ctr) = 38 (-1; -2)$ dB	$D_{n,e,w}(C;Ctr) = 55 (-2; -5)$ dB	2500
TA5221 + TA5202 (2500EA)	$D_{n,e,w}(C;Ctr) = 36 (0; -2)$ dB	$D_{n,e,w}(C;Ctr) = 55 (-1; -5)$ dB	2500
TA5221 + TA5005 (2500EA)	$D_{n,e,w}(C;Ctr) = 35 (0; -1)$ dB	$D_{n,e,w}(C;Ctr) = 54 (-1; -4)$ dB	2500
TA5220 + TA5202 (2500EA)	$D_{n,e,w}(C;Ctr) = 35 (0; -1)$ dB	$D_{n,e,w}(C;Ctr) = 55 (1; -5)$ dB	2500
TA5220 + TA5005 (2500EA)	$D_{n,e,w}(C;Ctr) = 32 (1; 0)$ dB	$D_{n,e,w}(C;Ctr) = 52 (-2; -4)$ dB	2500
TA5235 + TA5236 (5000EA)	$D_{n,e,w}(C;Ctr) = 40 (-2; -3)$ dB	$D_{n,e,w}(C;Ctr) = 51 (-1; -4)$ dB	5000

Manufactured from

Aluminium 6063A T6, component parts POM

Recommended screws

4mm (No.8) Round Head or equivalent

When fitting to PVCu screw must go through two walls or into reinforcement


Standards

Tested in accordance with BS EN 13141-1:2004 (airflow air leakage and weather tightness)

Finishes

Suffix product code with -20 (white)

Other colour options available. Please contact sales for details.



Through sash

Performance

(Full details available on request)

Equivalent Area – See above

Free Area – See above

Air Leakage – 0.11m³/hr @ 50Pa (Vent and Canopy only)

Water Resistance (Pa) – 750Pa

Acoustic $D_{n,e,w}$ – see above

NB: For optimum performance the ventilator should be installed on a flat surface free from defects, and sealant should be used along all edges to achieve the desired acoustic result.

More information

enquiries@titon.com / 01206 713801

