

Persimmon Homes Thames Valley

North Littlehampton, Toddington Lane / Spine Road Junction (S278 Works)

Stage 1 RSA – Road Safety Audit Response Report



Stage 1 RSA - Road Safety Audit Response Report

- 1.1 This report results from receipt of a Stage 1 RSA Report, undertaken by Traffic Management Consultants dated 12th January 2022.
- 1.2 The Designer's Response to the 'Problems' highlighted are indicated in the table below:

Item	Problem	Recommendation	Designer's Response	Overseeing Organisation Response	Agreed RSA Action
8.1	Location: Access to Tulley Cottages Summary: Access located close to junction give way resulting in insufficient space from right turn vehicles to wait before give way line. Type of Conflict/Collision: Vehicles blocking Toddington Lane south bound lane resulting in collisions.	Carry out vehicle swept path analysis to ensure access can be used safely without blocking south bound lane.	Accepted. A vehicles swept path analysis has been carried out for a large car exiting Tulley Cottages turning right and waiting behind another large car. The tracking shows the rear of a car waiting behind another car encroaches slightly onto the other lane. However, there is still sufficient room for vehicles travelling south bound.		

Persimmon Homes Thames Valley

North Littlehampton, Toddington Lane / Spine Road Junction (S278 Works)

Stage 1 RSA – Road Safety Audit Response Report



Item	Problem	Recommendation	Designer's Response	Overseeing Organisation Response	Agreed RSA Action
8.2	Location: Toddington Lane / Tulley Cottages access Summary: There is reduced visibility to the right of left turning vehicles from the spine road for vehicles exiting Tulley Cottages access. Ensure adequate visibility is provided at access. Type of Conflict/Collision: Collisions due to reduced visibility.	Ensure adequate visibility is provided.	Accepted. A visibility splay to the right of vehicles existing Tulley Cottages has been shown on the revised drawings. Please note this visibility is fundamentally unchanged in the revised junction. Visibility to the right is restricted by the presence of a hedge between Tulley Cottages and the Spine Road. There is a sign post within the visibility splay, which, however, doesn't reduce visibility significantly.		

Persimmon Homes Thames Valley
North Littlehampton, Toddington Lane / Spine Road Junction (S278 Works)
Stage 1 RSA – Road Safety Audit Response Report



On behalf of the Design Organisation I certify that:

- 1) The RSA actions identified in response to the road safety audit problems in this road safety audit have been discussed and agreed with the Overseeing Organisation.**

Name:	
Signed:	
Position:	
Organisation:	
Date:	

On behalf of the Overseeing Organisation I certify that:

- 1) The RSA actions identified in response to the road safety audit problems in this road safety audit have been discussed and agreed with the Design Organisation; and**
- 2) The agreed RSA actions will be progressed.**

Name:	
Signed:	
Position:	
Organisation:	
Date:	

Persimmon Homes Thames Valley
North Littlehampton, Toddington Lane / Spine Road Junction (S278 Works)
Stage 1 RSA – Road Safety Audit Response Report



Prepared by:

Name: Ivan Cosmai

Signed:

A handwritten signature in black ink, appearing to read 'Ivan Cosmai', written over a light blue rectangular stamp.

Position: Engineer

Organisation: Mayer Brown Limited

Date: 22/02/2022

Revision: P1