



A/PHLITTLE-MAIN.1/30-2

①	TYPE 0 - NO KERB
②	TYPE 1 - 125x255mm type H82 precast concrete kerb to BS EN 1340:2003 Figure NA.1(c) laid with 125mm upstand with ST1 concrete bed and backing
③	TYPE 2 - 125x150mm type BN precast concrete kerb laid 25mm for vehicular access to Figure NA.1(a) of BS EN 1340:2003 with mix ST1 concrete bed and backing.
④	TYPE 3 - 50x150mm type EF precast concrete flat top edging to Figure NA.3(a) of BS EN 1340:2003 with mix ST1 concrete bed and backing.
⑤	TYPE 4 - 125x255mm type H82 precast concrete kerb to BS EN 1340:2003 Figure NA.1(d) laid with 50mm upstand with ST1 concrete bed and backing
⑥	TYPE 5 - 125x150mm type BN precast concrete kerb laid flush (0 to 6mm) to Figure NA.1(e) of BS EN 1340:2003 with mix ST1 concrete bed and backing.
⑦	TYPE 6 - Marshalls 'Speeddeck' kerb (or similar approved) laid at bottom of ramp only, refer to (WSCC Detail S278/38/16)
⑧	KERB TYPE 7 - 125x255mm type CS1 precast concrete flat top kerb laid flush to adjoining surface to Figure NA.1(f) of BS EN 1340:2003 with mix ST1 concrete bed and backing.