PERSIMMON

tir

North Littlehampton: Central Wetland Area

Location of planting and features LA.**2**

LAP

LAP

LAP

MAIN AVENUE (20MPH)

Rd 1–Main Ave

SCHOOL SITE
1.3Ha

Key

- Existing Category A trees to be retained
- Existing Category B trees to be retained
- Existing Category C trees to be retained
- Root protection areas of existing trees
- Native tree and shrub planting: whips/transplants to be implemented from day 1.
- Native mix 2: tree and shrub planting: whips/transplants to be implemented from day 1.
- Proposed native tree planting: Standard/ Selected Standard/ Heavy Standard/ Extra Heavy Standard/ Semi-mature sizes/ Multi-stem to be implemented from day 1.
- Proposed species-rich grass/ natural regeneration: to be kept long and cut once a year
- Proposed species-rich grass: to be kept short and cut regularly throughout the year
- Grass reinforcement
- Hazel coppice
- Reed bed planting/ natural regeneration
- Marginal aquatics
- Bark mulch path through trees with stone edging. No dig through trees
- Depressions to capture and hold water for interest
- Lighting columns
- Timber bench (9no. including along top edge of wetland)
- Bin (9no. including along top edge of wetland)
- Jupiter Play (or similar) Trunk Pile
- Jupiter Play (or similar) Stepping Stilts
- Boulders
- Protection to shared use path: 1.5m high post and 3 rail timber fence
- Location of Swale crossings for maintenance of open space areas. For details of these crossings - refer to Engineers' details. Drawing No. MB_C_03 P4 - **Swale Crossing Point**.
- Location of reinforced grass Footpath / Ramp to LAP area. For details of this ramp - refer to Engineers' details. Drawing No. MB_C_03 P4 - **Section 10-10**.

0 10 20 30 40 50 metres

Scale 1:500 @ A0

North

TC22029_A088461-LA1-LA9[C].dwg

11th March 2022

tir collective LANDSCAPE ARCHITECTS

Britannia House, Caerphilly Business Park, Van Road, Caerphilly, CF83 3GG

© Tir Collective Limited 2022. Registered Company No. 13489264

ARUN DISTRICT COUNCIL LU/23/23/AOO