

DOE REF:TQ 00 SW 3/29 Toddington House [Formerly listed as no 257(including stables or barn at South end of south wing)]Stables and barn Garden shed immediately south-east of house

C16 or early C17 timber framed house now faced with brick and flints. 2 storey 'L' plan. West front: 1 window facing South and 3 facing West. South end single storey under catslide roof except for 2 storey projection with hipped gable over recessed entrance. Tall chimney at West end with stone quoins and octagonal stack. 1 storey shed joined to this, tiled with original Horsham slabs at base. Main house has tiles roof with later Horsham slabs at base. Casement windows. East front is 2 storeys, 6 windows. 2 brick flying butteresses (modern). Casement windows, 3 retaining brick mullions. Some panelling inside. North side has catslide roof. Garden shed immediately South-East of house. Skew plan. Cobbled walls with thatched roof. Stables to South of house, single storey timber with slate roof form 3 sides of a rectangle, the East side being a barn. Latter is weatherboarded, lower parts of cobble.]

DOE

LU/241/13/L