

The Studio, 68 Cuckfield Road, Hurstpierpoint, West Sussex BN6 9SB

Project Name: Proposed Residential Development - Toddington Lane, Littlehampton, West Sussex

Detailed Plant Schedule and Specification

Revision 01 / Date: 16th May 2019 – Detailed Planting List

					PLANTING AREAS														
					1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
Native Tree Planting																			
<i>Acer campestre</i> (Field Maple)	10-12 cm Girth Size / 3.0-3.5 m height / 1.75-2.0m Clear Stem / Standard Stock.	RB	Specimen	5	3											2			
<i>Carpinus betulus</i> (Hornbeam)	10-12 cm Girth Size / 3.0-3.5 m height / 1.75-2.0m Clear Stem / Standard Stock.	RB	Specimen	5	2		1									2			
<i>Malus sylvestris</i> (Crab Apple)	10-12 cm Girth Size / 3.0-3.5 m height / 1.75-2.0m Clear Stem / Standard Stock.	RB	Specimen	2				2											
Ornamental Tree Planting																			
<i>Acer campestre</i> 'Elegant'	10-12 cm Girth Size / 3.0-3.5 m height / 1.75-2.0m Clear Stem / Standard Stock.	RB	Specimen	9	2	7													
<i>Ulmus</i> 'Columella'	10-12 cm Girth Size / 3.0-3.5 m height / 1.75-2.0m Clear Stem / Standard Stock.	RB	Specimen	2								1	1						
Native Understorey Shrub Planting (60 - 90cm Multi branched)																			
<i>Acer campestre</i> (Field Maple)	60 - 90cm Multi Branched	BR	1/m ²	4				4											
<i>Cornus sanguinea</i> (Common Dogwood)	60 - 90cm Multi Branched	RB	1/m ²	13			3	4				3	3						
<i>Carpinus betulus</i> (Hornbeam)	60 - 90cm Multi Branched	RB	1/m ²	4				4											
<i>Corylus avellana</i> (Common Hazel)	60 - 90cm Multi Branched	RB	1/m ²	13			3	4				3	3						
<i>Crataegus monogyna</i> (Hawthorn)	60 - 90cm Multi Branched	RB	1/m ²	13			3	4				3	3						
<i>Ilex aquifolium</i> (Holly)	60 - 90cm Multi Branched	CG	1/m ²	7			3	4											
<i>Lonicera periclymenum</i> (Honeysuckle)	40-60 cm height.	CG / BR	1/m ²	3								3							
<i>Rosa canina</i> (Dog Rose)	40-60 cm height.	CG / BR	1/m ²	7				4					3						
<i>Salix caprea</i> (Goat Willow)	60 - 90cm Multi Branched	RB	1/m ²	4				4											
<i>Taxus baccata</i> (Yew)	60 - 90cm Multi Branched	RB	1/m ²	7			3	4											

RB: Root Ball / BR: Bare Root / CG: Container Grown

TODDINGTON LANE

DETAILED PLANT SCHEDULE AND SPECIFICATION

ARUN DISTRICT COUNCIL LU/248/19/DOC

PLANTING AREAS					1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
Native Wilder Species Hedgerow																			
<i>Acer campestre</i> (Field Maple) Hedging (10% of mix o/a)	60 – 90 cm height. Multi-Branched. (Hedging - 2 no. staggered rows set 400 mm apart @400 centres.)	BR	400mm Centres / 5m ²	59	23	23										13			
<i>Corylus avellana</i> (Common Hazel) Hedging (10% of mix o/a)	60 – 90 cm height. Multi-Branched. (Hedging - 2 no. staggered rows set 400 mm apart @400 centres.)	BR	400mm Centres / 5m ²	59	23	23										13			
<i>Crataegus monogyna</i> (Hawthorn) Hedging (10% of mix o/a)	60 – 90 cm height. Multi-Branched. (Hedging - 2 no. staggered rows set 400 mm apart @400 centres.)	BR	400mm Centres / 5m ²	59	23	23										13			
<i>Fagus sylvatica</i> (Beech) Hedging (10% of mix o/a)	60 – 90 cm height. Multi-Branched. (Hedging - 2 no. staggered rows set 400 mm apart @400 centres.)	BR	400mm Centres / 5m ²	60	24	23										13			
<i>Ilex aquifolium</i> (Holly) Hedging (10% of mix o/a)	60 – 90 cm height. Multi-Branched. (Hedging - 2 no. staggered rows set 400 mm apart @400 centres.)	BR	400mm Centres / 5m ²	60	24	23										13			
<i>Prunus spinosa</i> (Blackthorn) Hedging (50% of mix o/a)	60 – 90 cm height. Multi-Branched. (Hedging - 2 no. staggered rows set 400 mm apart @400 centres.)	CG	400mm Centres / 5m ²	301	121	115										65			
Ornamental Clipped Shrubs / Hedgerow																			
<i>Cotoneaster franchetii</i>	30-45cm height. Multi-Branched.	3 ltr CG	4 / m ²	11						11									
Ornamental Shrub Planting																			
<i>Choisya x dewitteana</i> 'White Dazzler'	30-45cm Ht / Spread	3 ltr CG	As Shown/3m ²	14							10			4					
<i>Hakonechloa macra</i>	30 – 40 cm Ht/Spread.	3 ltr CG	5/ m2	7						7									
<i>Hebe albicans</i> 'Red Edge'	20 – 30 cm height	3 ltr CG	4 / m2	6						6									
<i>Jasminum nudiflorum</i>	30-45cm Ht / Spread	3 ltr CG	As Shown/3m ²	11							11								
<i>Lavandula angustifolia</i>	30-45cm Ht / Spread	3 ltr CG	As Shown/4m ²	19							13			6					
<i>Lysimachia nummularia</i> 'Aurea'	30 – 40 cm spread	2ltr CG	5 / m2	17							9			8					
<i>Mahonia aquifolium</i> 'Apollo'	30-45cm Ht / Spread	3 ltr CG	As Shown/3m ²	12					6									6	
<i>Osmanthus x burkwoodii</i>	30-45cm Ht / Spread	3 ltr CG	As Shown/3m ²	8											8				
<i>Philadelphus</i> 'Bell Etoile'	30-45cm Ht / Spread	3 ltr CG	As Shown/3m ²	6											6				
<i>Sarcococca hookeriana</i> var. <i>humilis</i>	30-45cm Ht / Spread	3 ltr CG	As Shown/3m ²	25					13									5	7
<i>Skimmia japonica</i> 'Rubella'	30-45cm Ht / Spread	3 ltr CG	As Shown/3m ²	5											5				
<i>Viburnum davidii</i>	30-45cm Ht / Spread	3 ltr CG	As Shown/3m ²	11					4								4		3
<i>Viburnum opulus</i> 'Compactum'	30-45cm Ht / Spread	3 ltr CG	As Shown/3m ²	11						6	5								
<i>Viburnum tinus</i>	30-45cm Ht / Spread	3 ltr CG	As Shown/3m ²	13					6										7

					PLANTING AREAS														
Ornamental Shrub Climbers					1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
<i>Hydrangea petiolaris</i>	120 cm height. Cane Trained (To be trained up horizontal wires / wooden trellis)	5ltr Container Grown	Specimen	1							1								
<i>Lonicera periclymenum</i> 'Serotina'	120 cm height. Cane Trained (Shrubs to be trained up horizontal wires / wooden trellis)	5ltr Container Grown	Specimen	3										3					
<i>Lonicera periclymenum</i> 'Scentsation'	120 cm height. Cane Trained (Shrubs to be trained up horizontal wires / wooden trellis)	5ltr Container Grown	Specimen	2							2								
<i>Parthenocissus tricuspidata</i>	120 cm height. Cane Trained	5ltr Container	Specimen	3										3					
Wildflower and Grassland Mix FM2 STANDARD GENERAL PURPOSE MEADOW MIXTURE																			
Wildflowers		% of mix																	
<i>Achillea millefolium</i>	Yarrow	0.3																	
<i>Centaurea nigra</i>	Common Knapweed	3.5																	
<i>Daucus carota</i>	Wild Carrot	1.3																	
<i>Galium verum</i>	Lady's Bedstraw	3																	
<i>Knautia arvensis</i>	Field Scabious	0.5																	
<i>Leontodon hispidus</i>	Rough Hawkbit	0.2																	
<i>Leucanthemum vulgare</i>	Oxeye Daisy	0.5																	
<i>Lotus corniculatus</i>	Birdsfoot Trefoil	0.5																	
<i>Malva moschata</i>	Musk Mallow	2.5																	
<i>Plantago lanceolata</i>	Ribwort Plantain	1																	
<i>Primula veris</i>	Cowslip	1																	
<i>Prunella vulgaris</i>	Selfheal	1.7																	
<i>Ranunculus acris</i>	Meadow Buttercup	1.5																	
<i>Rhinanthus minor</i>	Yellow Rattle	2.5																	
Grasses																			
<i>Agrostis capillaris</i>	Common Bent	8																	
<i>Cynosurus cristatus</i>	Crested Dogtail	40																	
<i>Festuca rubra</i>	Slender-creeping Red-fescue	28																	
<i>Phleum bertolonii</i>	Smaller Cat's-tail	4																	