

SPECIFICATION
All works generally, to comply with the written Soft
Landscape Specification.

NOTES:
NOT FOR CONSTRUCTION, FOR PLANNING
PURPOSES ONLY

Legend

- Proposed tree planting within soft landscape.
See detail 2 on sheet 2
- Proposed tree planting within root cell tree pit
for constrained or hard landscape areas.
See detail 1 on sheet 2
- Proposed specimen shrub planting to receive
short angular staking on half standards with
expandable tree ties. Irrigation tubing to root
system as required
- Proposed mixed native hedge planting to be
planted in a double staggered row 500mm
apart and at 400mm centres in each row. To be
maintained at 1m height and 1.8m height
adjacent to site boundaries
- Proposed formal hedge planting to be planted
in a double staggered row 300mm apart and at
400mm centres in each row.
- Proposed tactile and sensory ornamental
grasses and shrub planting
- Proposed shrub planting to receive 75mm
bark mulch after planting operations
- Proposed decorative mix shrub planting to be
planted in groups of 5-7no. of each species and
as above
- Proposed native scrub planting mix to be
planted in groups of 5-7no. of each species and
as above
- Proposed bulb mix.
- Proposed grass areas to receive good quality
amenity grass turves laid in line with good
horticultural practices
- Proposed meadow mix, to be seeded with EM3
special general purpose mix as supplied by
Emorsgate Seed and sown at 4 grams per
sq. or equivalent
- Proposed Flowering Lawn, to be seeded with
EL1 Flowering lawn mixture as supplied by
Emorsgate Seed and sown at 4 grams per
sq. or equivalent
- Hoggin path with timber edging to existing
PRoW
- Proposed rain garden planting to be planted in
groups of 5-7no. of each species and as above
- Proposed incidental play feature see hard
landscape for further detail.



B	17.06.26	Revised Layout	LS
A	28.05.26	Revised Layout	RH
Rev	Date	Details	Drawn



HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01666 825646

4 & 5 The Old Mill, Fry's Yard, Bridge Street,
Codalming, GU7 1HP
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close,
Eastleigh, SO50 9SX
Tel: 02382 026300

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk



scheme: Hampton Park
Littlehampton

client: Persimmon Thames Valley
drawing: Soft Landscape Proposals
Local Centre

date: November 2025
scale: 1:200@A1 Sheet 5 of 5

drawing no: PERTV24807 11
drawn: RH checked: DKM

Copyright of ACD Environmental Ltd. All rights described in
Chapter IV of the Copyright, Designs and Patents Act 1988
have been generally asserted. 2011. Copyright of this plan
remains with ACD until all fees have been paid in full.

