



EAST TO WORTHING
& BRIGHTON
RUSTINGTON BY-PASS A259
WEST TO CHICHESTER &
PORTSMOUTH



New Tree Planting
(Standard 8-10 &
10-12)
T1. Betula Pendula
T2. Acer Hyrcanum
T3. Robinia Pseudoacacia

Boundary Treatment

To Be 1.8m high fence panel = P
To Be 1.1m high fence panel = PI
To Be 2.0m high close boarded = Cb
To Be 2.5m high acoustic fence = Bp



New Acoustic Fence
Height 2.50m
Set in Conc Base Min 900mm For 2.50m post
125mm x 100mm Posts @ 1.8 c/c
Cladding 150mm x 22mm boards with 50mm gap
Second layer 100mm x 22mm boards fixed over gaps min cover 25mm
Mass 26.5 kg/m2 based on softwood of 530 kg/cu m

Landscaping Key

- Existing grassed area
- New grass turf
- New tarmac road
- Brick paviours
- Paving slabs
- New concrete footpath

New native mixed hedging consisting of:
Crataegus monogyna (hawthorn) 40%
Prunus spinosa (Blackthorn) 20%
Corylus avellana (Hazel) 20%
Acer campestre (Field Maple) 20%
Height 90-120cm, supported with canes and
protected by guards and anti-weed matting.

B	Planting added along new acoustic fence.	08.08.14
A	Plots 1 & 2 garages moved, car parking space removed.	16.06.14

REV	DESCRIPTION	DATE
REVISION		

job no.	drawing no.	rev.
023 001	110	B

scale	drawn by	date
1:200 @ A1	ACB	30/05/2013

Residential Development
The Poplars (Former HRI Site)
Worthing Road, Littlehampton
West Sussex. BN17 6GZ

SITE LANDSCAPING PLAN



Rustington House, Worthing Road, Rustington, West Sussex, BN16 3PS
Tel No: (01903) 777777 Fax No: (01903) 777700