




© Mayer Brown Limited Copyright. The drawings, information and data recorded in this document ("the information") is the property of Mayer Brown. This document and the information are made for the use of the addressee recipient and this document may not be used, copied or reproduced in any form or by any means other than the written consent supplied by Mayer Brown. Mayer Brown makes no representation, warranties or duty and accepts no responsibility for any third party who may rely on or use the information or the information.

A0 ORIGINAL

KEY

PROPOSED KERB/EDGING LINE

PROPOSED DROPPED KERB

PROPOSED BUFF COLOURED TACTILE PAVING

BS category A Trees of high quality
BS category B Trees of moderate quality

BS category C Trees of low quality

BS category U Trees unsuitable for retention

Estimated tree positions not included on original land survey and adjusted crown spreads

Purpose of this plan and its annotation

This constraints plan provides sufficient information to interpret the tree constraints when designing a new layout. This guidance must be carefully reviewed with the individual tree information provided in the schedule on this plan. If there is any doubt about how to interpret this information, you must check it out with Barrell Tree Consultancy (BTC) on 01425 651470 or info@barrelltreecare.co.uk.

The number of each tree, hedge and group is highlighted in colour to enable quick identification of tree categories. Category A and B trees are green, category C and U trees are blue. The number of each A and B tree is set inside a green triangle, the number of each C and U tree is set inside a blue rectangle. Category A trees are shown with double triangles and U trees are shown with double rectangles. Zone 1, indicating the RPA where no ground disturbance should occur, is annotated with dark shading. Zone 2, indicating where shading, dominance and/or future growth may be an issue, is annotated with light shading.

How to use the constraints information

Our interpretation of the starting-point recommendations of BS 5837(2012) is that only category A and B trees are sufficiently important to influence a layout, so the category C and U trees are discounted in this constraints advice. The constraints that the A and B trees are likely to impose have been assessed as follows:

Zone 1 (dense coloured shading): This is called the root protection area (RPA) where ground disturbance must be carefully controlled. If encroachment is planned within the RPA, then this must be assessed on a tree-by-tree basis by BTC. If important trees are to be successfully retained, no significant disturbance should occur within the RPA and a high level of care is needed when working within it.

Zone 2 (light coloured shading): The second constraint is where shading/dominance/future growth may be an issue and is our estimate of how much space may be needed to retain trees after the development activity when the pressures of residential occupation come to bear. Factors such as crown density, future growth potential, orientation in relation to the sun and the number of trees in groups are considered to arrive at this second, less restrictive, constraints zone. Zone 2 is not normally suitable for occupied buildings, but uninhabited structures and hard surfacing may be acceptable within it.

Zone 3: Nominal RPA radii for category C trees: Low quality only to be considered for retention if there is scope within the layout and they do not compromise the potential to establish new trees of higher future sustainability.

FOR INFORMATION NOT FOR CONSTRUCTION

P4	Chevron signing & cordony paving added following Stage 1 & 2 received 13/07/17. (PB)	AB	19/07/2017
P3	Uncontrolled crossing point added at the northern end of the TDR and Red Line added. (DIN)	AB	07/07/2017
P2	Western arm updated and Northern arm amended following meeting with WSCC and Capital. (DIN)	AB	14/06/2017
P1	Initial issue. (DIN)	AB	07/12/2016

rev.	amendment	checked	date
------	-----------	---------	------



Mayer Brown Limited
Lion House, Oriental Road, Woking, Surrey GU24 0AR
Telephone 01483 750 508 Fax 01483 750 437
workingoffice@mayerbrown.co.uk www.mayerbrown.co.uk

Client
PERSIMMON HOMES

Project
NORTH LITTLEHAMPTON
SOUTHERN BYPASS WORKS

Scale 1:250 Drawn by PB Checked by AB

Date NOVEMBER Cad file TR-1 P4 & TR-2 P4.DWG

Title
PROPOSED S38/S278 HIGHWAY WORKS
SOUTHERN BYPASS ROUNDABOUT
TREE REMOVAL DRAWING

Drawing number A/PHLYM.1/TR-1 Revision P4