



From: Sarah Burrow <Sarah.Burrow@arun.gov.uk>
Sent: 23 December 2020 10:26
To: Planning.Responses <Planning.Responses@arun.gov.uk>
Subject: RE: Planning Consultation on: LU/284/20/PL

Engineers Comments Regarding Surface Water Drainage

The hierarchy for sustainable drainage should be followed and soakaways fully investigated. However, despite reducing the mass of the building from application LU/125/19/PL there still appears to be insufficient room for surface water drainage within the curtilage of the new site. Soakaways must be located 5m from buildings, and should be located 2.5m from property boundaries.

Mapping indicates that Arundel Road is at risk of surface water flooding. There are no other sources for surface water disposal except disposal to the foul sewer. This should be an absolute last resort, will be resisted by ourselves and may be turned down by the sewerage undertaker.

Therefore I **object** to the proposals.

To overcome my objection the applicant should complete winter groundwater monitoring and winter infiltration testing and complete calculations to assess the size of structures required. A rough plan should be formed showing where these structures can be provided within the proposed layout. Detailed design of the system can be left until discharge of conditions where the applicant should provide the level of information stated within our checklist <https://www.arun.gov.uk/drainagechecklist>.

However if you are minded to approve the application please apply the following condition:

PCENG2

"Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity."

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the accompanying informative:

INFORMD

"Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The percolation tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year event plus 40% on stored volumes, as an allowance for climate change. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest winter groundwater table in support of the design. The applicant is advised to discuss the extent of groundwater monitoring with the Council's Engineers.

Supplementary guidance notes regarding surface water drainage are located here

<https://www.arun.gov.uk/surfacewater> on Arun District Councils website. A surface water drainage checklist is available on Arun District Councils website, this should be submitted with a Discharge of Conditions Application."


Kind Regards

Sarah Burrow

Engineering Assistant, Engineering Services

T: 01903 737815

E: sarah.burrow@arun.gov.uk



Current working hours: Mon 8:00-2:30, Tues-Thur 8:00-17:30, Fri 8:00-11:30

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF

www.arun.gov.uk

Sign up to our newsletter [here](#)



From: Planning.Responses <Planning.Responses@arun.gov.uk>

Sent: 16 November 2020 08:49

To: Land Drainage [REDACTED]

Subject: Planning Consultation on: LU/284/20/PL

To: Engineers (Drainage)

NOTIFICATION FROM ARUN DISTRICT COUNCIL

Town & Country Planning Act 1990 (as amended)

Town and Country Planning (Development Management Procedure) (England) Order 2015

Planning Permission

Application No: LU/284/20/PL
Registered: 13th November 2020
Site Address: 54 Arundel Road Littlehampton BN17 7DD
Grid Reference: 502732 102451
Description of Works: Demolition of 3 No. garages & erection of a four-room house of multiple occupation with shared facilities & parking for 3 cars (resubmission of LU/125/19/PL).

The Council have received the above application.

[Click here to view the application details](#)

This application has been identified as CIL Liab. Therefore please be aware that, in accordance with Appendix 2 of the Arun CIL Charging Schedule, your consultation response should only include requests for Section 106 for on site mitigation, Pagham Harbour Management Contributions (if applicable) or Affordable Housing. Off Site mitigation measures directly related to this development should be dealt with by condition if possible to ensure the scaling back of Section 106 if possible. CIL contributions will be used for off site infrastructure mitigation schemes. Therefore if this proposal triggers the need for off site mitigation, please ensure that you engage in the CIL Infrastructure List Consultation process upon receipt of a consultation letter.

Should you have any comments to make, these should be sent by replying to this email by 17th December 2020 . You can also monitor the progress of this application through the Council web site:

www.arun.gov.uk/planning.

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website <https://www.arun.gov.uk/development-plan> as can the the leaflet how to respond to planning applications <https://www.arun.gov.uk/planning-application-comments> which deals with material planning considerations.

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: <https://www.planningportal.co.uk/info/200207/appeals> but they will protect personal details.

In the absence of a reply within the period stated, I shall assume that you have no observations to make

Yours sincerely

Andrew Wood

Planning Officer- Arun District Council

Telephone: 01903 737768

Email: andrew.wood@arun.gov.uk

PLCONSULT (GOB) 2020