

	Project Linden Park, Littlehampton				Job no. 19119	
	Calcs for Surface Water drainage Soakaway				Start page no./Revision 4	
	Calcs by PSG	Calcs date 21/11/2019	Checked by	Checked date	Approved by	Approved date

SOAKAWAY DESIGN

In accordance with BRE Digest 365 - Soakaway design

Tedds calculation version 2.0.04

Design rainfall intensity

Location of catchment area

Brighton

Impermeable area drained to the system

$A = 551.5 \text{ m}^2$

Return period

Period = 100 yr

Ratio 60 min to 2 day rainfall of 5 yr return period

$r = 0.350$

5-year return period rainfall of 60 minutes duration

$M5_{60\text{min}} = 20.0 \text{ mm}$

Increase of rainfall intensity due to global warming

$p_{\text{climate}} = 30 \%$

Soakaway / infiltration trench details

Soakaway type

Rectangular

Minimum depth of pit (below incoming invert)

$d = 1206 \text{ mm}$

Width of pit

$w = 2500 \text{ mm}$

Length of pit

$l = 20000 \text{ mm}$

Percentage free volume

$V_{\text{free}} = 95 \%$

Soil infiltration rate

$f = 8.90 \times 10^{-6} \text{ m/s}$

Wetted area of pit 50% full

$a_{s50} = l \frac{1}{4}d + w \frac{1}{4}d = 27127549 \text{ mm}^2$

Table equations

Inflow (cl.3.3.1)

$I = M100 \frac{1}{4}A$

Outflow (cl.3.3.2)

$O = a_{s50} \frac{1}{4}f \frac{1}{4}D$

Storage (cl.3.3.3)

$S = I - O$

Duration, D (min)	Growth factor Z1	M5 rainfalls (mm)	Growth factor Z2	100 year rainfall, M100 (mm)	Inflow (m³)	Outflow (m³)	Storage required (m³)
5	0.36;	9.3;	1.89;	17.6;	9.68;	0.07;	9.61
10	0.51;	13.2;	1.96;	25.8;	14.25;	0.14;	14.10
15	0.62;	16.0;	2.00;	32.0;	17.67;	0.22;	17.45
30	0.79;	20.5;	2.03;	41.5;	22.88;	0.43;	22.44
60	1.00;	26.0;	2.00;	52.1;	28.71;	0.87;	27.84
120	1.22;	31.8;	1.96;	62.2;	34.30;	1.74;	32.56
240	1.50;	38.9;	1.90;	73.9;	40.75;	3.48;	37.27
360	1.69;	43.9;	1.86;	81.7;	45.04;	5.22;	39.82
600	1.95;	50.6;	1.81;	91.4;	50.41;	8.69;	41.71
1440	2.48;	64.5;	1.71;	110.4;	60.86;	20.86;	40.00

Required storage volume

$S_{\text{req}} = 41.71 \text{ m}^3$

Soakaway storage volume

$S_{\text{act}} = l \frac{1}{4}d \frac{1}{4}w \frac{1}{4}V_{\text{free}} = 57.27 \text{ m}^3$

PASS - Soakaway storage volume

Time for emptying soakaway to half volume

$t_{s50} = S_{\text{req}} \frac{1}{4}0.5 / (a_{s50} \frac{1}{4}f) = 23\text{hr } 59\text{min } 40\text{s}$

PASS - Soakaway discharge time less than or equal to 24 hours