

Specification No. 4366

6th November 2014

Ms Viktorija Saveca
Stiles Harold Williams
69 Park Lane
CROYDON
CR0 1BY

Dear Ms Saveca

Re: Unit 31 Eldon Way

Thank you for your enquiry. Further to our recent telephone conversation, I have pleasure in confirming the following specification, which I trust will be acceptable.

SPECIFICATION

- The new roller shutters will be constructed from single skin, 75 mm curved galvanised laths.
- All mild steel components are treated with rust inhibiting metal primer.
- Manual or electric operation is available:-

Manual hand chain mechanism, complete with padlockable chain keep.

Operation via 3-phase industrial motor complete with internal limits and emergency override facility. The motor to be wired back to a suitable live power supply, preinstalled by others outside the scope of this quotation, to within 500 mm of the opening.

Single phase tube motors or single phase flange mounted motors are available within certain limitations.

- Polyester powder paint finish is available for the laths, guides, angles and end plates at an additional cost.
- Barrel size and lath gauge are determined by the overall size and location of the door.
- Insulated laths are available, these are 100 mm deep and double skinned complete with a cfc free foam core.

I hope the above meets with your requirements. Please contact me if you have any queries or need any additional information.

Yours sincerely

JOHN JACKSON
Sales Manager

Security • Strength • Reliability

Sterling House
Eridge Road
Crowborough
East Sussex TN6 2SY