



— Ramp with 1200 x 1200 level platform, 1:15 gradient. 1200mm clear width with brick upstand along each edge

— Kee Klamp galvanised handrail system 900mm high with 550mm high mid rail, extending 300mm from bottom of the ramp

NOTES:

1. All dimensions are in mm and must be checked on site.
2. Drawings are to be read in conjunction with accompanying documents.
3. Any errors or inaccuracies should be brought to the attention of Amber Living.

Revision	Description	By	Date

Contact Information

Unit 3, Tungsten Building, George Street,
Portslade, Brighton, BN41 1RA

Tel: 01273 410836
Email: heather@amberliving.co.uk





Client Name

Mrs Daphne Wells

Address

38 Seaton Park, Wick, Littlehampton

Drawing Title

Proposed Front Access

Drawing Reference

HT/02/SeatonPark38

Date

28/11/19

Scale	Paper	Drawn By	Revision	Direction
1: 20	A2	HT	A	