

NOTES

Scheme has been designed to meet standards of BS5489 for Car Parks.

Average Level 5 Lux and Uo of 25%

Any questions regarding these drawings should be addressed to: Simon Tibble at Holophane Lighting 07764 336805 or stibble@holophane.co.uk

All dimensions should be checked, the design assumes that there will be no obstructions.

Holophane Europe Limited offer a Lighting Design Service in good faith and without charge. Every effort is made to ensure we interpret design briefs accurately and in turn provide suitable and detailed proposals. However, the final responsibility for the design and any recommendations offered lies with the client, customer. Checking that any proposal meets current Standards or clients requirements is the responsibility of the customer.

Holophane Europe Limited does not therefore accept any liability for loss or damage incurred for design misinterpretation.

Results provided within this proposal are derived from specific product photometry; the substitution of luminaires either with alternative Holophane luminaires or from other manufacturers products may not produce the same results.

LUMINAIRE LOCATIONS							
No.	Label	Location		Z	MH	Orientation	Tilt
		X	Y				
1	A	28.5	51.5	6.0	6.0	269.4	0.0
2	A	29.4	27.4	6.0	6.0	264.0	0.0
3	A	57.2	31.3	6.0	6.0	-87.3	0.0
4	A	22.9	16.8	6.0	6.0	1.1	0.0
5	A	36.3	38.2	6.0	6.0	179.0	0.0
6	B	11.9	5.3	1.0	1.0	102.4	0.0
7	B	6.4	1.7	1.0	1.0	192.6	0.0
8	B	14.4	15.4	1.0	1.0	120.3	0.0
9	B	65.6	-24.6	1.0	1.0	19.6	0.0
10	B	57.6	-18.1	1.0	1.0	32.1	0.0
11	B	51.0	11.0	1.0	1.0	202.5	0.0

STATISTICS						
Description	Symbol	Avg	Max	Min	Min/Max	Min/Avg
Calc Zone #1	+	N / A	N / A	N / A	N / A	N / A
Chessboard Area	□	N / A	N / A	N / A	N / A	N / A
Path 1	+	N / A	N / A	N / A	N / A	N / A
Path 2	+	N / A	N / A	N / A	N / A	N / A



LUMINAIRE SCHEDULE									
Symbol	Label	Qty	Catalog Number	Description	Lamp	File	Lumens	LLF	Watts
	A	5	QSS.42TRT.CG C4(F) DEFAULT	QSS WITH CURVED GLASS	42W TRT 4000K COMPACT FLUORESCENT 4-PIN (GX24q-4)	B071116.IES	3200	0.88	0
	B	6	DBL.42PL4.PAY.S O	DENVER BOLLARD	42W TRT 4000K COMPACT FLUORESCENT 4 PIN (GX24q-4)	B99217.IES	3200	0.88	0

