



NEW PLANTING SCHEDULE

Shrubs	Abbrev	Species Name	No.	Height	Pot Size
BtAN	Berberis thunbergii	'Atropurpurea Nana'	11 No.	20-30cm	
CT.	Choisya ternata		5 No.	30-40cm	
CaE	Cornus alba	'Elegantissima'	18 No.	40-60cm	
CH.	Cotoneaster horizontalis		26 No.	30-40cm	
EEG	Euonymus fortunei	'Emerald 'n' Gold'	23 No.	15-20cm	
EfSQ	Euonymus fortunei	'Silver Queen'	28 No.	20-30cm	
FTT	Fuchsia	'Tom Thumb'	4 No.	20-30cm	
GL.	Genista	lydia	11 No.	30-40cm	
HMB	Hebe	'Midsummer Beauty'	4 No.	30-40cm	
HRE	Hebe	'Red Edge'	5 No.	20-30cm	
HPP	Hebe pinguifolia	'Pagei'	10 No.	20-30cm	
Hm	Hypericum	moserianum	110 No.	30-40cm	
LM	Lavandula angustifolia	'Munstead'	23 No.	15-20cm	
LP.	Lonicera pileata		28 No.	20-30cm	
PB	Perovskia	'Blue Spire'	14 No.	20-30cm	
PfRR	Photinia fraseri	'Red Robin'	11 No.	40-60cm	
PIOL	Prunus laurocerasus	'Otto Luyken'	26 No.	30-40cm	
PC	Pyracantha coccinea	'Lalandei'	46 No.	60-80cm	
PRC	Pyracantha coccinea	'Red Cushion'	10 No.	30-40cm	
RMJ	Rosmarinus officinalis	'Miss Jessopp's Upright'	40 No.		5L
VD.	Viburnum davidii		9 No.	20-30cm	
VT.	Viburnum tinus		26 No.	30-40cm	
			Total :488 No.		

Herbaceous	Abbrev	Species Name	No.	Pot Size
BB	Bergenia cordifolia		21 No.	2L
			Total :21 No.	

Trees	Abbrev	Species Name	No.	Girth	Specification
PA.	Prunus 'Amanogawa'		2 No.	10-12cm	CG
SA	Sorbus aucuparia		2 No.	10-12cm	CG
			Total :4 No.		

KEY :

	NEW TREES
	SHRUB PLANTING
	HEDGE PLANTING
	GRASS (TURF)

Notes

HARD LANDSCAPE FINISHES:

See separate architects drawings for hard landscape finishes, fencing and wall details. This drawing is only to be used for setting out tree, plant and turfing works only

GROUND WORKS:

All ground works and top soil to be in accordance with section D20 of the project landscape specification

EXISTING TREES:

Existing levels to be preserved around all existing trees. No permanent or temporary loading is to impose within three metres of each existing tree. All existing trees should be adequately protected prior to construction works commencing

Any necessary tree works are to be carried out by an approved tree surgeon to BS 3998

PLANTING ETC:

General plant stock to conform with BS 3936 and BS 5236 and planting to be undertaken in full accordance with the project landscape specification

All planting areas and isolated tree beds to be mulched with a medium grade bark mulch to a depth of 50mm

Foundations to dwellings to be designed to take account of mature height of existing and proposed trees

MAINTENANCE:

Establishment maintenance for all planting for 1 year from planting date to include weed control and grass cutting

Revisions:

A - Revised layout June 2013

DESIGN CONSULTANCY & CONSTRUCTION



LANDSCAPES LIMITED
Brick Kiln Nursery, Bognor Road, Merston, Chichester,
West Sussex. PO20 1EJ

Telephone 01243 531700 Facsimile 01243 539933

Project:

LITTLEHAMPTON MARKET

Planting Layout:

Scale: 1:200 @ A1 Date: MAY 2013

Dimensions to be verified on site prior to construction. Do not scale this drawing, use figured dimensions only. Copyright reserved. Under no circumstances must this drawing be used for landscaping purposes without the express prior permission of VDW Landscapes Limited.

Main Contractor:

AUSTIN BUILDERS

Drawing Number: TND 25114-1A

© 2013 VDW Landscapes Limited