



Plant schedule					
Number	Abbreviation	Species	Specification	Girth	Height
39 -	Ac	Acer campestre	Selected standard: 2x: B	10-12cm	300-350cm
13 -	AgI	Alnus glutinosa	Multi stem: 3x: RB		250-300cm
12 -	AgI	Alnus glutinosa	Semi mature: 3x/4x: RB	20-25cm	350-400cm
15 -	BEPE	Betula pendula	Semi mature: 3x/4x: RB	20-25cm	350-400cm
19 -	BEPE	Betula pendula	Multi stem: 3x: RB		250-300cm
8 -	BEPE	Betula pendula	Selected standard: 2x: RB	10-12cm	300-350cm
7 -	MALSY	Malus sylvestris	2x: Standard; clear stem 175-200cm; 4 breaks; B	8-10cm	250-300cm
8 -	PRUIAV	Prunus avium	3x: Extra Heavy Standard; clear stem 175-200cm; 5 breaks; B	14-16cm	400-450cm
23 -	PRUIA	Prunus padus	3x: Extra Heavy Standard; clear stem 175-200cm; 5 breaks; RB	14-16cm	400-450cm
8 -	Qr	Quercus robur	Extra heavy: 3x: RB	18-20cm	450-500cm
5 -	Qr	Quercus robur	Selected standard: 2x: RB	10-12cm	300-350cm
6 -	Sa	Salix alba	Extra heavy: 3x: B	16-18cm	400-450cm
6 -	Sa	Salix alba	Selected standard: 2x: B	10-12cm	300-350cm
9 -	SALFR	Salix fragilis	Selected standard: 2x: B	10-12cm	300-350cm
19 -	Sau	Salix aucuparia	Extra heavy: 3x: B	16-18cm	400-450cm
33 -	TcGS	Tilia cordata 'Green Spire'	Extra heavy: 3x: RB	16-18cm	450-500cm

Native mix					
Number	Abbreviation	Species	Specification	Height	Pot Size
258 -	CORSA	Cornus sanguinea	1+1; Transplant - seed raised; branched; 3 breaks; B	60-80cm	1.25Ctr
227 -	Cav	Corylus avellana	1+2 or 1/2: Branched :B :3 brks	60-80cm	1.25Ctr
385 -	Cmo	Crataegus monogyna	1+1 or 1/1: B	60-80cm	1.25Ctr
319 -	Ia	Ilex aquifolium	Leader with laterals; C	60-80cm	3L
353 -	L vu	Ligustrum vulgare	0/2: Cutting; branched; 3 breaks; B	60-80cm	1.25Ctr
227 -	PRUSP	Prunus spinosa	1+1 or 1/1: B: Branched :2 brks	60-80cm	1.25Ctr
163 -	RHAFR	Rhamnus frangula	1+1; Transplant - seed raised; leader with laterals; 3 breaks; B	60-80cm	1.25Ctr
163 -	ROSCA	Rosa canina	1+1; Transplant - seed raised; branched; 3 breaks; B	60-80cm	1.25Ctr
258 -	SACA	Salix caprea	0/1: B: Branched :2 brks	60-80cm	1.25Ctr
227 -	SLCI	Salix cinerea	0/1: B: Branched :2 brks	60-80cm	1.25Ctr
163 -	SALVI	Salix viminalis	1+0 or 1/0: Branched :B	30-40cm	1.25Ctr
258 -	SAMNI	Sambucus nigra	1+1 or 1/1: B: Branched :3 brks	60-80cm	1.25Ctr
227 -	VIBOP	Viburnum opulus	1+2 or 1/2: B: Branched :3 brks	60-80cm	1.25Ctr
Total :3228 - Note: Evergreen species and Rosa canina to be positioned on drier land					

- S: Standard
SS: Selected Standard
HS: Heavy Standard
EHS: Extra Heavy Standard
SM: Semi Mature
MS: Multi-Stem
- Key
- Existing Category A trees to be retained
 - Existing Category B trees to be retained
 - Existing Category C trees to be retained
 - Root protection areas of existing trees
 - Native tree and shrub planting: whips/transplants to be implemented from day 1.
 - Proposed native tree planting: Standard/ Selected Standard/ Heavy Standard/ Extra Heavy Standard/ Semi-mature sizes/ Multi-stem to be implemented from day 1.
 - Proposed species-rich grass/ natural regeneration: to be kept long and cut once a year
 - Proposed species-rich grass: to be kept short and cut regularly throughout the year
 - Reed bed planting/ natural regeneration
 - Depressions to capture and hold water for interest
 - Lighting columns
 - Timber bench
 - Bin
 - Protection to shared use path (knee rail)