



Plant schedule

Number	Abbreviation	Species	Specification	Grth	Height
39	Ac	Acer campestre	Selected standard: 2x: B	10-12cm	300-350cm
13	-	Agl	Alnus glutinosa	Multi stem: 3x: RB	250-300cm
9	-	Agl	Alnus glutinosa	Semi mature: 3x/4x: RB	20-25cm 550-600cm
15	-	BEPE	Betula pendula	Semi mature: 3x/4x: RB	20-25cm 550-600cm
19	-	BEPE	Betula pendula	Multi stem: 3x: RB	250-300cm
8	-	BEPE	Betula pendula	Selected standard: 2x: RB	10-12cm 300-350cm
7	-	MALSY	Malus sylvestris	2x: Standard; clear stem 175-200cm; 4 breaks; B	6-10cm 250-300cm
8	-	PRUAV	Prunus avium	3x; Extra Heavy Standard; clear stem 175-200cm; 5 breaks; B	14-16cm 400-450cm
23	-	PRUAV	Prunus padus	3x; Extra Heavy Standard; clear stem 175-200cm; 5 breaks; RB	14-16cm 400-450cm
5	-	QUE ILE	Quercus ilex	3x; Extra Heavy Standard; clear stem 175-200cm; RB	18-20cm 450-625cm
6	-	Qr	Quercus robur	Extra heavy: 3x: RB	18-20cm 450-500cm
5	-	Qr	Quercus robur	Selected standard: 2x: RB	10-12cm 300-350cm
6	-	Sa	Salix alba	Extra heavy: 3x: B	16-18cm 400-450cm
6	-	Sa	Salix alba	Selected standard: 2x: B	10-12cm 300-350cm
9	-	SALFR	Salix fragilis	Selected standard: 2x: B	10-12cm 300-350cm
19	-	Sau	Sorbus aucuparia	Extra heavy: 3x: B	16-18cm 400-450cm
33	-	TcGS	Tilia cordata 'Green Spire'	Extra heavy :3x :RB	16-18cm 450-500cm

Number	Abbreviation	Species	Specification	Pot Size	Height	Density
54	-	CORAV	Corylus avellana	Branched; 4 breaks; C	10L	80-100cm Counted

Number	Abbreviation	Species	Specification	Height	Pot Size	Density	Percentage Contribution
194	-	CORSA	Cornus sanguinea	1+1; Transplant - seed raised; branched; 3 breaks; B	60-80cm	1.25Cr	9%
150	-	Cav	Corylus avellana	1+2 or 1/2 : Branched :B :3 brks	60-80cm	1.25Cr	7%
265	-	Cmo	Crataegus monogyna	1+1 or 1/1 : B	60-80cm	1.25Cr	12%
150	-	I a	Ilex aquifolium	Leader with laterals; C	60-80cm	3L	1.25Cr 7%
150	-	L.vu	Ligustrum vulgare	0/2; Cutting; branched; 2 breaks; B	60-80cm	1.25Cr	7%
150	-	PRUSP	Prunus spinosa	1+1 or 1/1 : B: Branched :2 brks	60-80cm	1.25Cr	7%
108	-	RHAFR	Rhamnus frangula	1+1; Transplant - seed raised; leader with laterals; 3 breaks; B	60-80cm	1.25Cr	5%
108	-	ROSCA	Rosa canina	1+1; Transplant - seed raised; branched; 3 breaks; B	60-80cm	1.25Cr	5%
171	-	SACA	Salix caprea	0/1 :B :Branched :2brks	60-80cm	1.25Cr	9%
150	-	SLCI	Salix cinerea	0/1 : B :Branched :2 brks	60-80cm	1.25Cr	7%
108	-	SALVI	Salix viminalis	1+0 or 1/0 :Branched :B	30-40cm	1.25Cr	5%
171	-	SAMNI	Sambucus nigra	1+1 or 1/1 : B :Branched :3brks	60-80cm	1.25Cr	10%
131	-	TAX BAC	Taxus baccata	Leaders; feathered to base; C	40-60cm	3L	1.25Cr 6%
150	-	VIBOP	Viburnum opulus	1+2 or 1/2 : B :Branched :3 brks	60-80cm	1.25Cr	7%
Total :2147 - Note: Evergreen species and Rosa canina to be positioned on drier land							

Number	Abbreviation	Species	Specification	Density	Pot Size	Height	Percentage Contribution
77	-	Cav	Corylus avellana	1+2 or 1/2 : Branched :B :3 brks	1.25Cr	60-80cm	7%
129	-	EUOAL	Eucynmus alatus	Branched; 3 breaks; C	1.25Cr	3L	30-40cm 12%
77	-	I a	Ilex aquifolium	Leader with laterals; C	1.25Cr	3L	60-80cm 7%
77	-	L.vu	Ligustrum vulgare	0/2; Cutting; branched; 3 breaks; B	1.25Cr	60-80cm	7%
129	-	POP ALB	Populus alba	0/1; Cutting; B	1.25Cr	60-80cm	12%
66	-	RHAFR	Rhamnus frangula	1+1; Transplant - seed raised; leader with laterals; 3 breaks; B	1.25Cr	60-80cm	6%
77	-	ROSCA	Rosa canina	1+1; Transplant - seed raised; branched; 3 breaks; B	1.25Cr	60-80cm	7%
87	-	SACA	Salix caprea	0/1 :B :Branched :2brks	1.25Cr	60-80cm	8%
66	-	SALVI	Salix viminalis	1+0 or 1/0 :Branched :B	1.25Cr	30-40cm	6%
107	-	SAMNI	Sambucus nigra	1+1 or 1/1 : B :Branched :3brks	1.25Cr	60-80cm	10%
66	-	TAX BAC	Taxus baccata	Leaders; feathered to base; C	1.25Cr	40-60cm	6%
129	-	VIBOP	Viburnum opulus	1+2 or 1/2 : B :Branched :3 brks	1.25Cr	60-80cm	12%
Total :1087 - Note: Evergreen species and Rosa canina to be positioned on drier land							

Number	Abbreviation	Species	Specification	Pot Size	Density	Percentage Contribution
356	-	CarObt	Carex otrubae	Full pot; Sept to April planting; British native-origin; C	1L	0.45Cr 30%
439	-	F.vu	Filipendula ulmaria	Full pot; Sept to April planting; British native-origin; C	1L	0.45Cr 30%
294	-	IRIPS	Iris pseudacorus	Full pot; C	0.5L	0.45Cr 20%
371	-	L sa	Lythrum salicaria	Full pot; C	0.5L	0.4Cr 20%
Total :1460 -						

Number	Abbreviation	Species	Specification	Pot Size	Density	Percentage Contribution
704	-	GLY VAR	Glyceria maxima 'Variegata'	Plug; established root 2-3 months minimum; Sept to April planting; British native-origin; 50c min	0.7Cr	25%
704	-	PHA ARU	Phalaris arundinacea	Full pot; Sept to April planting; British native-origin; C	1-1.5L	0.7Cr 25%
843	-	PHR	Phragmites	Full pot; June to Sept planting; British native-origin; C	1-1.5L	0.7Cr 30%
282	-	TYPLA	Typha latifolia	Full pot; C	1L	0.7Cr 10%
282	-	TYPMI	Typha minima	Full pot; C	1L	0.7Cr 10%
Total :2815 -						

- S: Standard


SS: Selected Standard

HS: Heavy Standard

EHS: Extra Heavy Standard


SM: Semi Mature

MS: Multi-Stem
- Key

 Existing Category A trees to be retained

 Existing Category B trees to be retained

 Existing Category C trees to be retained

 Root protection areas of existing trees

 Native tree and shrub planting: whips/transplants to be implemented from day 1.

 Native mix 2: tree and shrub planting: whips/transplants to be implemented from day 1.

 Proposed native tree planting: Standard/ Selected Standard/ Heavy Standard/ Extra Heavy Standard/ Semi-mature sizes/ Multi-stem to be implemented from day 1.

 Proposed species-rich grass/ natural regeneration: to be kept long and cut once a year

 Proposed species-rich grass: to be kept short and cut regularly throughout the year

 Hazel coppice

 Reed bed planting/ natural regeneration


 Marginal aquatics


 Bark mulch path through trees with stone edging. No dig through trees

 Depressions to capture and hold water for interest


 Lighting columns


 Timber bench (9no. including along top edge of wetland)

 Bin (9no. including along top edge of wetland)

 Jupiter Play (or similar) Trunk Pile

 Jupiter Play (or similar) Stepping Stilts

 Boulders

 Protection to shared use path: 1.5m high post and 3 rail timber fence

Ecology note

Given that the land within the proposed central wetland largely comprised buildings and hardstanding with limited areas of vegetation which comprised managed grassland and scattered trees. The proposed landscaping scheme is considered to provide biodiversity net gain through the provision of biodiverse, native species habitats including: native tree and shrub planting, new native tree planting, species rich grassland to develop into a long sward length, reed bed planting and aquatic vegetation.

SCHOOL SITE
1.3Ha