© Mayer Brown Limited Copyright. The drawings, information and data recorded in this document ("the information") is the property of Mayer Brown. This document and the information are solely for the use of the authorised recipient and this document may not be used, copied or reproduced in whole or part for any purposes other than which it was supplied by Mayer Brown. Mayer Brown makes no representation, undertakes no duty and accepts no responsibility to any third party who may use or rely upon this document or the information.

A0 ORIGINAL

© Crown copyright and database rights 2019. Ordnance Survey 0100031673.

KEY

- PROPOSED SURFACE WATER SEWER TO BE ADOPTED BY ICOSA UNDER S.104 AGREEMENT
- PROPOSED SURFACE WATER MANHOLE CHAMBER TO BE ADOPTED BY ICOSA UNDER S.104 AGREEMENT
- PROPOSED SURFACE WATER VORTEX SEPARATOR DOWNSTREAM DEFENDER CHAMBER TO BE ADOPTED BY ICOSA UNDER S.104 AGREEMENT
- PROPOSED SURFACE WATER FLOW CONTROL CHAMBER TO BE ADOPTED BY ICOSA UNDER S.104 AGREEMENT
- PROPOSED SURFACE WATER ATTENUATION STORAGE TO BE ADOPTED BY ICOSA UNDER S.104 AGREEMENT
- PROPOSED SURFACE WATER HEADWALL TO BE ADOPTED BY ICOSA UNDER S.104 AGREEMENT
- PROPOSED FOUL WATER SEWER TO BE ADOPTED BY ICOSA UNDER S.104 AGREEMENT
- PROPOSED FOUL WATER MANHOLE CHAMBER TO BE ADOPTED BY ICOSA UNDER S.104 AGREEMENT
- SOUTHERN WATER PUMPING STATION
- PROPOSED PRIVATE SURFACE WATER SYSTEM
- PROPOSED PRIVATE SURFACE WATER FIN DRAIN
- PROPOSED PRIVATE SURFACE WATER PERFORATED PIPE
- PROPOSED PRIVATE FOUL WATER SYSTEM
- PROPOSED HIGHWAY DRAINAGE SYSTEM
- PROPOSED PERMEABLE SUB-BASE SURROUNDED WITH PERMEABLE GEOTEXTILE, WITHIN PRIVATE ROAD
- PROPOSED PERMEABLE SUB-BASE SURROUNDED WITH IMPERMEABLE GEOTEXTILE, WITHIN PRIVATE ROAD
- SITE BOUNDARY

NOTES:

1. This drawing is not to be scaled.
2. This drawing is to be read in conjunction with all other relevant engineering and landscaping drawings. Any discrepancies are to be reported to the Engineer immediately for clarification.
3. Proprietary items are to be constructed in accordance with manufacturers recommendations and requirements.
4. All drainage works shall be carried out in accordance with the requirements of all adopting authorities, the Local Authority, the Environment Agency and in conjunction with all relevant British Standards, Codes of Practice and 'Sewers for Adoption' 6th Edition and any addendums as appropriate.
5. Invert levels and positions of existing sewer where new connections are to be made must be checked and confirmed prior to the commencement of any works.
6. All drainage shall comply with the typical details and the requirements of BS EN 752 and Part H of the Building Regulations.
7. All precast concrete units used in the drainage works shall be manufactured using sulphate resisting cement.
8. Manhole covers and frames shall be to BS EN 124 and shall be Kitemarked. The strength classes of covers are shown in the manhole schedules.
9. Cover levels are to be adjusted locally to suit finished ground levels.

FOR APPROVAL
NOT FOR CONSTRUCTION

rev.	amendment	checked	date
P4	Revisions clouded. (IC)	SL	26/09/2019
P3	Additional details added (clouded). (IC)	SL	29/07/2019
P2	Revisions clouded. (IC)	SL	11/07/2019
P1	Initial Issue (JS)	SL	01/03/2019

mayer brown
Mayer Brown Limited
Lion House Oriental Road Woking Surrey GU22 8AR
Telephone 01483 750 508 Fax 01483 750 437
wokingoffice@mayerbrown.co.uk www.mayerbrown.co.uk

client: PERSIMMON HOMES THAMES VALLEY

project: NORTH LITTLEHAMPTON

scale: 1:250 @ A0 | drawn by: JS | checked by: SL

date: MARCH 2019 | cad file: S104 ICOSA.DWG

title: SECTION 104 DRAINAGE GENERAL ARRANGEMENT SURFACE AND FOUL WATER - SHEET 4 OF 4

Mayer Brown Limited jobcode: A/PHLITTLE-INT.10 | suitability: - | revision: P4

drawing number: A/PHLITTLE-INT.10/S104-10-4

ARUN DISTRICT COUNCIL LU/375/19/DOC