ARUN DISTRICT COUNCIL:LU/37/06/ 06/02/2006

RIVER BAR.

RESTAURANT.

DINING AREA.

FOOD SERVERY.

PREP AREA.

KITCHEN

DISABLED TOILET.

LADIES. TOILETS.

GENTS. TOILETS.

BAR SERVERY

BAR SERVERY.

STORE

LOBBY

ALTER / MAKE GOOD EXISTING CONCRETE STAIRCASE TO SUIT UP. NEW LAYOUT.

UP 120mm

REMOVED EXISTING DOOR & FRAME

LADIES. TOILETS.

MALE TOILETS.

BAR AREA.

CELLAR.

STORE.

STORE.

COLD STORE

EXISTING REFRIGERATION CHAMBERS

EXISTING REFRIGERATION CHAMBER

NEW STORE EXTENSION

PAVEMENT

NEW STORE EXTENSION

NOTE.

The Contractor is to check and verify all building and site dimensions, levels and service invert levels at connection points before work starts. This drawing must be read with and checked against any structural or other specialist drawings provided.

The Contractor is to comply in all respects to with the current building Regulations whether or not specifically stated on these drawings.

This drawing is not intended to show details of foundations or ground conditions. Excavations of ground reduced by or to support the sides and adjacent must be broadly agreed by the Contractor on site from the results of Landscape Consultant's

ARUN DISTRICT COUNCIL
No.
RECEIVED

A	CLIENT AMENDMENTS	–	FEB'06
REV		By	Date

Hunting Design
architecture and planning consultants

Client ENTERPRISE INNS.

Site THE ARUN VIEW LITTLEHAMPTON.

Title PROPOSED. GROUND. FLOOR PLAN.

Project No. and Standard	Drawn by –L–	Scale 1:50	Date JAN'06.
Acad. File	Drawing No. 06:12/02		A