© Mayer Brown Limited Copyright. The drawings, information and data recorded in this document ("the information") is the property of Mayer Brown Limited. The information is provided solely for the use of the authorised recipient and this document may not be used, copied or reproduced in whole or part for any purposes other than which it was supplied by Mayer Brown. Mayer Brown makes no representation, undertakes no duty and accepts no responsibilities to any third party who may use or rely upon this document or the information.

A0 ORIGINAL

© Crown copyright and database rights 2022. Ordnance Survey 0100031673.

KEY


- EXISTING KERB LINE
- PROPOSED KERB/EDGING LINE
- PROPOSED DROPPED KERB
- KERB LINE FUTURE WORKS
- PROPOSED 2.4m X 25m JUNCTION VISIBILITY SPLAY
- PROPOSED 25m PEDESTRIAN VISIBILITY SPLAY
- PROPOSED 25m FORWARD VISIBILITY AROUND BEND
- DIAG 1234 — PROPOSED ROAD MARKING
- PROPOSED BUFF COLOURED TACTILE BLISTER PAVING
- PROPOSED CORDUROY HAZARD WARNING PAVING
- PROPOSED 6 METRE COLUMN FITTED WITH POST TOP MOUNTED LUMINAIRE WITH 5 DEGREE TILT. LUMINAIRE TO BE PHILLIPS DIGISTREET MICRO BGP760 DW50, LED-HB 5.1S CW, 5.4KKLM. LUMINAIRE TO BE FITTED WITH ELECTRONIC DIMMABLE BALLAST COMPATIBLE WITH MAYFLOWER CMS VIA DALI PROTOCOL. LUMINAIRE IS TO BE CONTROLLED VIA A MAYFLOWER EXTERNAL NODE. COLUMN TO BE PAINTED BS12B21 (GREEN).
- LIMIT OF WORKS ASSOCIATED WITH MAIN AVENUE

NOTES:

1. This drawing is not to be scaled.
2. Drawing based on Banners Gate Engineering Base drawing reference " X_21044 - Engineering Base", received on 22/06/2022.
3. Based on topographic survey by Subvision Surveys undertaken in March 2022.
4. This drawing is to be read in conjunction with all other relevant engineering and landscaping drawings. Any discrepancies are to be reported to the Engineer immediately for clarification.

KEY TO HEALTH AND SAFETY SYMBOLS

	INDICATES A RESIDUAL RISK REQUIRING A COMPULSORY ACTION.
	INDICATES A RESIDUAL RISK FOR INFORMATION.
	INDICATES A RESIDUAL RISK REQUIRING A PROHIBITIVE ACTION.
	INDICATES A RESIDUAL RISK AS A WARNING.



FOR TENDER
NOT FOR CONSTRUCTION

rev.	amendment	checked	date
T9	Drawing updated following meeting with WSCC on 04/05/22. (TC)	IC	15/06/2022
T8	Streetlighting added and key updated. (TC)	SF	26/05/2022
T7	Parallel crossing removed. (TC)	IC	19/04/2022
T6	Drawing updated following RSA comments received on 12/01/22 and comments from WSCC dated 08/02/22. (TC)	IC	24/02/2022
T5	Parallel crossing added near community centre. Kerbs added across raised tables and at vehicle crossovers onto soft landscaping. (IC)	SF	06/01/2022
T4	Revised Architect's layout received on 22/11/2021. Internal layout updated. No changes to Main Avenue Road design. (TC)	SF	24/11/2021
T3	Drawing updated following comments from RSA received on 12/08/21. (TC)	SF	26/08/2021
T2	3m wide verge added to main avenue. Junction locations amended following revised phase 5 layout and foul pumping station relocated. (TC)	SF	26/05/2021
T1	Initial Issue. (TC)	SF	18/03/20

mayer brown

Mayer Brown Limited
Lion House Oriental Road Woking Surrey GU22 8AR
Telephone 01483 750 508 Fax 01483 750 437
wokingoffice@mayerbrown.co.uk www.mayerbrown.co.uk

client
PERSIMMON HOMES THAMES VALLEY

project
NORTH LITTLEHAMPTON
EAST OF WETLANDS
MAIN AVENUE & NORTHERN CROSSING

scale	drawn by	checked by
1:250	TC	SF

date	cad file
OCTOBER 2019	10.DWG

title
GENERAL ARRANGEMENT DRAWING
(SHEET 2 OF 3)

Mayer Brown Limited jobcode	suitability	revision
		T9

drawing number
A/PHLITTLE-MAIN.1/10-2