

40 LTR SUPERIOR EPOXY COATED STAINLESS STEEL GREASE TRAP

PERFECT FOR COMMERCIAL KITCHENS:

- 40 litre capacity
- Comes with full instructions for easy installation
- Free couplings! Ensure a watertight connection
- Connects to standard 2" pipework (50mm)
- Use indoors, outdoors or below ground
- Neoprene sealed lids preventing unwanted odours
- 5 Year warranty
- Designed to meet water company requirements

DESCRIPTION

PERFECT FOR COMMERCIAL KITCHENS:

- 40 litre capacity
- Comes with full instructions for easy installation
- Connects to standard 2" pipework (50mm)
- Use indoors, outdoors or below ground
- Neoprene sealed lids preventing unwanted odours
- 5 Year warranty
- Designed to meet water company requirements

Durable corrosion free, high quality steel construction with fully welded seams for improved strength and durability.

COMPLIES WITH:

- BS EN 1825-1:2004

DESIGNED IN ACCORDANCE WITH:

- BS EN 1825-2:2002.

KEY FEATURES:

- Minimise drain cleaning call-out charges
- Improve wastewater discharge quality
- Eliminate unwanted, nasty odours
- Corrosion free construction

TECHNICAL INFORMATION:

Model: RIX-7KGEC23

Dimensions (MM):460 x 340 x 310 (l x w x h)

Inlet/Outlet (MM):50

Grease Capacity (KG):7

Liquid Holding Capacity (L):40

Meals Per Day: Approximately to 80 – 100

Flow Rate (L.P.M):27

Height To Outlet (MM):190



Outlet