




From: [REDACTED]
Sent: 23 March 2022 09:28
To: Harry Chalk <Harry.Chalk@arun.gov.uk>
Cc: [REDACTED]
Subject: RE: Drainage Consultation on: M/12/22/HH


CAUTION: This email originated from outside of the organisation. You should take extra care when clicking links or opening attachments - if you are unsure the content is safe contact the IT Helpdesk before clicking or opening.

Hi Harry

We agree to the condition.

Kind regards

Leeza Aldis-Hobbs
Chartered Architect ARB RIBA SPAB
AMdesign Architects


www.amdesignltd.co.uk

From: Harry Chalk <Harry.Chalk@arun.gov.uk>
Sent: 22 March 2022 11:56
To: 
Subject: FW: Drainage Consultation on: M/12/22/HH

Hello Leeza,

I have received the below consultation from our Drainage Engineers and I am in agreement that this is a substantial increase in impermeable surface area within the Lidsey Treatment Catchment area that needs to be monitored. I would ask that this pre-commencement condition is agreed to before any decision can be made. Could I request, if agreeable, that you respond with confirmation of agreement for this condition to be applied?

Kind regards,

Harry

Harry Chalk
Planning Officer, Development Management

T: 01903 737577
E: harry.chalk@arun.gov.uk

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk



Sign up to our newsletter [here](#)



From: Sarah Burrow <Sarah.Burrow@arun.gov.uk>
Sent: 17 March 2022 11:50
To: Planning.Responses <Planning.Responses@arun.gov.uk>
Cc: Harry Chalk <Harry.Chalk@arun.gov.uk>
Subject: RE: Planning Consultation on: M/12/22/HH

Engineers Comments Regarding Surface Water Drainage

The application is within the Lidsey Treatment Catchment, therefore surface water drainage design should be carefully considered. Infiltration must be fully investigated.

The applicant's architect states on the flood mitigation statement that the addition to the floor print will have minimum impact and that they intend to utilise the existing surface water drainage arrangement. We disagree with this statement. We will strongly oppose any connection of surface water to the foul sewer and would expect the surface water drainage for the new extension to meet current requirements.

If you are minded to approve the application please apply the following conditions to ensure that the development is adequately drained and does not increase flood risk elsewhere.

PCENG2

"Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity."

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

And the accompanying informative:

INFORMD

"Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The infiltration tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method. All design storms must include a climate change allowance of 40% on stored volumes or rainfall intensity. Infiltration structures must cater for the critical 1 in 10 year storm event, (plus 40%) between the invert of the entry pipe to the soakaway and the base of the structure. The design must also have provision to ensure there is capacity in the system to contain the critical 1 in 100 year storm event (plus 40%)."

Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate groundwater monitoring data to determine the highest groundwater table in support of the design. The applicant is advised to discuss the extend of ground water monitoring with the council's engineers.

Supplementary guidance notes regarding surface water drainage are located at <https://www.arun.gov.uk/drainage-planning-consultations> on Arun District Council's website. A surface water drainage checklist is available on Arun District Council's website, this should be submitted with a Discharge of Conditions Application."

Kind regards

Sarah Burrow

Engineering Assistant, Engineering Services

T: 01903 737815

E: sarah.burrow@arun.gov.uk



Current working pattern: Monday-Friday, 8am - 2:30pm

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk

Sign up to our newsletter [here](#)



From: Planning.Responses <Planning.Responses@arun.gov.uk>

Sent: 14 February 2022 12:49

To: Land Drainage <Land.Drainage@arun.gov.uk>

Subject: Planning Consultation on: M/12/22/HH

To: **Engineers (Drainage)**

NOTIFICATION FROM ARUN DISTRICT COUNCIL

Town & Country Planning Act 1990 (as amended)

Town & Country Planning (Development Management Procedure) (England) Order 2015

Planning Permission for Works or Extension to a Dwelling

Application No: M/12/22/HH
Registered: 11th February 2022
Site Address: 9 Sunnymead Close Middleton-on-sea PO22 6LS
Grid Reference: 498327 100514
Description of Works: Erection of single storey rear extension.

The Council have received the above application.

[Click here to view the application details](#)

Should you have any comments to make, these should be sent by replying to this email by 17th March 2022 . You can also monitor the progress of this application through the Council web site:

<https://www.arun.gov.uk/planning-application-search>

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website

<https://www.arun.gov.uk/development-plan> as can information on what comments we can consider

<https://www.arun.gov.uk/planning-application-comments>

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: <https://app.planninginspectorate.gov.uk/> but they will protect personal details.

When the appeal relates to a householder application there will be no opportunity to make further comments.

In the absence of a reply within the period stated, I shall assume that you have no observations to make

Yours sincerely

Harry Chalk

Planning Officer- Arun District Council

Telephone: 01903 737577

Email: harry.chalk@arun.gov.uk

<http://www.arun.gov.uk>

DX 57406 Littlehampton

You can view Arun District Council's Privacy Policy from <https://www.arun.gov.uk/privacy-policy>

Important Notice This e-mail is intended exclusively for the addressee and may contain information that is confidential and/or privileged. If you are not the intended recipient (or authorised to receive it for the addressee), please notify the sender and delete the e-mail immediately; using, copying, or disclosing it to anyone else, is strictly prohibited and may be unlawful. Any views, opinions or options presented are solely those of the author and do not necessarily represent those of Arun District Council. The information in this e-mail may be subject to public disclosure under the Freedom of Information Act 2000, therefore we cannot guarantee that we will not provide the whole or part of this e-mail to a third party. The Council reserves the right to monitor e-mails in accordance with relevant legislation. Whilst outgoing e-mails are checked for viruses, we cannot guarantee this e-mail is virus-free or has not been intercepted or changed and we do not accept liability for any damage caused. Any reference to "e-mail" in this disclaimer includes any attachments.
