

Hole dug @ White Horse
 9 Hair Drive, H-o-S on
 Sunday 9th Feb 2014
 1 metre square and 1.2 metres
 deep
 13.35



Hole @ White Horse, 9, Main Drive
H.O.S on Sunday 9th Feb 2014
one hour + later @ 14.50
showing water level of 2cm



Cedral Weatherboard

Product data and colour range

Cedral Weatherboard, Cherque Farm, Hampshire



Cedral Weatherboard, Repton Park, Ashford, Kent



Availability

Some colours are available on short lead times. Please contact the Customer Services team for details.

Cedral Weatherboard is sold in pallet quantities of 144 planks.

Bespoke colours are subject to minimum order quantities of 576 planks and subject to extended lead times.

Aluminium trims

Supplied in colours to match and complement Cedral Weatherboard.

Standards

The technical properties of Cedral Weatherboard sheets are in accordance with the prescriptions of BS EN 12467: 2004, Category A, Class 2.

Manufacture

Cedral Weatherboard is an autoclaved fibre cement plank manufactured from a mixture of cement, organic fillers and water.

Touch up paint

Cedral Weatherboard touch up paint is available in 0.5 litre quantities.

Cedral Weatherboard Woodstain

Cut edges of Cedral Weatherboard woodstain must be sealed with Luko solution.

Dimensions

Length	3600mm
Width	190mm
Thickness	10mm
Weight/board	11.2kg

Properties (air dry)

Installed weight	19.3kg/m ²
Density	1300kg/m ³
Bending strength:	Longitudinal 23N/mm ² Transverse 11N/mm ²
Modulus of elasticity:	Longitudinal 7500N/mm ² Transverse 5500N/mm ²
Expansion from dry air to saturated	1.75mm/m
Thermal conductivity	0.212W/mK
Reaction to fire:	Building Regulations Class 0
EN 13501-1	A2-s1, d0