



Tree	Number	Species	Height	Birth	Specification	Density
151	No.	Acer campestre	350-425cm	14-16cm	Heavy Standard: 5 brks: 3x: RB: Clear Stem 175-200cm	12/m ²
4	No.	Acer campestre	350-425cm	14-16cm	Heavy Standard: 5 brks: 3x: RB: Clear Stem min. 200cm	12/m ²
4	No.	Acer campestre	350-425cm	14-16cm	Extra Heavy Standard: 5 brks: 3x: RB: Clear Stem min. 200cm	12/m ²
2	No.	Amelanchier lamarkii	350-425cm	14-16cm	Transplant: seed raised: Branches: 3 breaks	12/m ²
2	No.	Corpus betulus	350-425cm	14-16cm	Heavy Standard: 5 brks: 3x: RB: Clear Stem 175-200cm	12/m ²
456	No.	Crataegus monogyna	350-425cm	14-16cm	Heavy Standard: 5 brks: 3x: RB: Clear Stem 175-200cm	12/m ²
2	No.	Fagus sylvatica	350-425cm	14-16cm	Heavy Standard: 5 brks: 3x: RB: Clear Stem 175-200cm	12/m ²
3	No.	Prunus padus	350-425cm	14-16cm	Standard: 5 brks: 3x: RB: Clear Stem 175-200cm	12/m ²
2	No.	Quercus robur	350-425cm	14-16cm	Heavy Standard: 5 brks: 3x: RB: Clear Stem 175-200cm	12/m ²

Shrub	Number	Species	Height	Birth	Specification	Density
142	No.	Ceanothus 'Blue Mound'	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
239	No.	Chamaecyparis	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
116	No.	Cornus sanguinea 'Midwinter Fire'	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
115	No.	Cornus sanguinea 'Midwinter Fire'	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
28	No.	Hebe 'Great Orme'	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
28	No.	Hebe 'Wiri Charm'	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
6	No.	Ilex aquifolium	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
13	No.	Ilex aquifolium	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
280	No.	Lavandula angustifolia 'Hidcote'	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
8	No.	Lavandula angustifolia 'Munstead'	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
51	No.	Lavandula angustifolia 'Munstead'	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
155	No.	Lavandula x intermedia 'Alba'	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
6	No.	Ligustrum vulgare	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
33	No.	Ligustrum vulgare	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
6	No.	Rosa canina	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
33	No.	Rosa canina	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
195	No.	Spiraea japonica 'Candlelight'	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
2	No.	Viburnum opulus	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²
33	No.	Viburnum opulus	20-30cm	14-16cm	Branches: 4 brks: 4/m ²	12/m ²

Herbaceous	Number	Species	Height	Birth	Specification	Density
13	No.	Acmella ludoviciana 'Silver Queen'	20-30cm	14-16cm	Full Pot: 2	12/m ²
28	No.	Bergenia 'Silverlicht'	20-30cm	14-16cm	Group 5/6: 4 Buds: Full Pot: 2	12/m ²
15	No.	Bergenia cordifolia	20-30cm	14-16cm	Full Pot: 2	12/m ²
44	No.	Iris 'Jane Phillips'	20-30cm	14-16cm	Full Pot: 2	12/m ²
36	No.	Lychnis flos-cuculi	20-30cm	14-16cm	Full Pot: 2	12/m ²
134	No.	Salvia officinalis	20-30cm	14-16cm	Full Pot: 2	12/m ²
17	No.	Stachys palustris	20-30cm	14-16cm	Full Pot: 2	12/m ²
124	No.	Stachys palustris	20-30cm	14-16cm	Full Pot: 2	12/m ²
66	No.	Thymus vulgaris	20-30cm	14-16cm	Full Pot: 2	12/m ²
23	No.	Veronica prostrata	20-30cm	14-16cm	Full Pot: 2	12/m ²

LEGEND

Proposed Standard Tree Planting

Proposed Specimen Shrub

Proposed Mixed Small Shrub & Herbaceous Planting

Proposed Mixed Shrub Planting

Proposed Amenity Grass Areas
Mx: Emorsgate EL1 Flowering Lawn Mx Sown
At 4g/m² or similar approved

Proposed Wildflower Area
Mx: Emorsgate EM2 General Purpose
Meadow Mixture Sown at 4g/m²
or similar approved

Proposed Bog Garden

Proposed Infilled Native Hedgerow

Existing Trees
to be Retained and Protected

Proposed Native Hedgerow

Existing Ditch
to be Retained and Protected

Proposed Amenity Grass Mix - Emorsgate EL1 Flowering Lawn Mix

To Be Sown At 4g/m²:

Wild Flowers	%	Latin name	Common name
4	%	Galium verum	Lady's Bedstraw
0.5	%	Leontodon hispidus	Rough Hawkbit
1	%	Leucanthemum vulgare	Oxeye Daisy
3.7	%	Lotus corniculatus	Birdsfoot Trefoil
3	%	Primula veris	Cowslip
4	%	Prunella vulgaris	Selfheal
3.5	%	Ranunculus acris	Meadow Buttercup
0.3	%	Trifolium pratense	Wild Red Clover
20	%		
Grasses	%	Latin name	Common name
8	%	Agrostis capillaris	Common Bent
40	%	Cynosurus cristatus	Crested Dogtail
28	%	Festuca rubra	Slender-creeping Red-fescue
4	%	Phleum bertolonii	Smaller Cat's-tail
80	%		

Proposed Wild Flower Seed Mix - Emorsgate EM2 General Purpose Meadow Mix

To Be Sown At 4g/m²:

Wild Flowers	%	Latin name	Common name
1	%	Achillea millefolium	Yarrow
5	%	Centaurea nigra	Common Knapweed
3	%	Galium verum	Lady's Bedstraw
0.5	%	Leucanthemum vulgare	Oxeye Daisy
0.5	%	Lotus corniculatus	Birdsfoot Trefoil
1	%	Plantago lanceolata	Ribwort Plantain
0.5	%	Plantago media	Hoary Plantain
1	%	Primula veris	Cowslip
1	%	Prunella vulgaris	Selfheal
2	%	Ranunculus acris	Meadow Buttercup
1	%	Ranunculus bulbosus	Bulbous Buttercup
2.4	%	Rhinanthus minor	Yellow Rattle
1	%	Rumex acetosa	Common Sorrel
0.1	%	Trifolium pratense	Wild Red Clover
20	%		
Grasses	%	Latin name	Common name
8	%	Agrostis capillaris	Common Bent
40	%	Cynosurus cristatus	Crested Dogtail
28	%	Festuca rubra	Slender-creeping Red-fescue
4	%	Phleum bertolonii	Smaller Cat's-tail
80	%		

0

HD

x

08/20

INTERNAL LAYOUT UPDATE

Revision

By

CHK'd By

Date

Comments

SAILORS BETHEL
HORATIO STREET
NEWCASTLE UPON TYNE
TYNE AND WEAR, NE1 2PE
T: 0191 261 1966
F: 0191 230 2346
www.slrconsulting.com

Site

MIDDLETON-ON-SEA

Project

LANDSCAPE ASSESSMENT

Drawing Title

SOFTWORKS PLAN

Scale

1:200 @ A1

Date

AUGUST 2020

Drawing Number

402.6594.00008.RC.002

Revision

0

PLANNING ISSUE