

STP245S - 20/Wd
STP240S - 20/Wd

SUNTECH
Solar powering a green future™

245 Watt MONOCRYSTALLINE SOLAR MODULE

Features

- 14.8%** High module conversion efficiency (up to 14.8%), through superior manufacturing technology
- 0-5%** Guaranteed 0-5% positive power output tolerance ensures high return on investment
- Suntech's TruPower™** process neutralizes the initial LID effect
- Self-clean** Anti-reflective, hydrophobic coating improves light absorption and reduces surface dust
- 3 bus bar** Three bus-bar design enhances cell reliability and reduces series resistance for large fill factor
- Weak light** Excellent performance under low light environments (mornings, evenings and cloudy days)
- 2400Pa 5400Pa** Entire module certified to withstand high wind loads (2400 Pascal) and snow loads (5400 Pascal) *



Trust Suntech to Deliver Reliable Performance Over Time

- World's leading manufacturer of crystalline silicon photovoltaic modules
- Unrivaled manufacturing capacity and world-class technology
- Rigorous quality control meeting the highest international standards: ISO 9001:2008 and ISO 14001:2004
- Certification and standards: IEC 61215, IEC 61730, conformity to CE

Industry-leading warranty

25-year transferable power output warranty:
5 years/95%, 12 years/90%, 18 years/85%, 25 years/80%
Based on nominal power
Warrants 6.7% more power than the market standard over 25 years
5 years material and workmanship warranty




Specialty designed drainage holes and rigid construction prevent frame from deforming or breaking due to freezing weather and other forces



Latest IP67 rated junction box improves module stability with enhanced thermal isolation


Please refer to Suntech Standard Module Installation Manual for details.
Please refer to Suntech Product Warranty for details.

STP245S - 20/Wd
STP240S - 20/Wd



Note: unit (inch)

Current-Voltage & Power-Voltage Curve (240S-20)



Temperature Characteristics

Nominal Operating Cell Temperature (NOCT)	45±2°C
Temperature Coefficient of Pmax	-0.48 %/°C
Temperature Coefficient of Voc	-0.34 %/°C
Temperature Coefficient of Isc	0.037 %/°C



Specifications are subject to change without further notification

Electrical Characteristics

STC	STP245S-20/Wd	STP240S-20/Wd
Optimum Operating Voltage (Vmp)	30.5 V	30.2 V
Optimum Operating Current (Imp)	6.04 A	7.55 A
Open - Circuit Voltage (Voc)	37.3 V	37.2 V
Short - Circuit Current (Isc)	6.32 A	6.43 A
Maximum Power at STC (Pmax)	243 W	240 W
Module Efficiency	14.8%	14.5%
Operating Temperature	-40 °C to +85 °C	-40 °C to +85 °C
Maximum System Voltage	1000 V DC	1000 V DC
Maximum Series Fuse Rating	20 A	20 A
Power Tolerance	0±5%	0±5%

STC: Irradiance 1000 W/m², module temperature 25 °C, AM=1.5

NOCT	STP245S-20/Wd	STP240S-20/Wd
Maximum Power (W)	180 W	177 W
Maximum Power Voltage (V)	27.9 V	27.6 V
Maximum Power Current (A)	6.45 A	6.40 A
Open Circuit Voltage (Voc)	34.3 V	34.2 V
Short Circuit Current (Isc)	6.89 A	6.81 A
Efficiency Reduction (from 1000 W/m² to 200 W/m²)	<4.5%	<4.5%

NOCT: Irradiance 800 W/m², ambient temperature 30 °C, wind speed 1 m/s

Mechanical Characteristics

Solar Cell	Monocrystalline 156 x 156 mm (6 inches)
No. of Cells	60 (6 x 10)
Dimensions	1665 x 991 x 50 mm (65.6 x 39.0 x 2.0 inches)
Weight	20.0 kgs (44.1 lbs.)
Front Glass	3.2 mm (0.13 inches) tempered glass
Frame	Anodized aluminum alloy
Junction Box	IP67 rated
Output Cables	H+S RADON® SMART cable 4.0 mm² (10.086 inches²), symmetrical lengths (3.1000 mm (39.4 inches) and (4) 1000 mm (39.4 inches), RADON® SOLAR integrated twist locking connectors

Packing Configuration

Container	20' GP	40' HQ
Pieces per pallet	21	21
Pallets per container	6	28
Pieces per container	126	588

PA/13/11/Case