

Amex users: Your banking app may briefly show a higher amount during checkout. You'll only be charged the correct total. We're working to resolve this issue.

SHOP BY CATEGORIES

Ceiling Lights	+
Wall Lights	+
Recessed Lighting	+
Bathroom Lighting	+
Kitchen Lighting	+
Track Lighting	+
Integrated Lighting	+
Outdoor Lighting	+
Commercial Lighting	+
Floor and Table Lamps	+
Ceiling Fans	+
Lighting Gift Ideas	
Bulbs, Lamps and Accessories	+
Shop by Design Look	+
Stock Clearance	

LED DOWNLIGHT FULL IP65 PROTECTION ABOVE & BELOW SOFFITS - CORROSION-RESISTANT & CCT

Dimmable Versatile CCT LED Downlight – Double Insulated & IP65 Rated for Outdoor Use



Product Ref: 54969

From £16.20 inc VAT

Description More Details Q & A's

This LED downlight distinguishes itself with several key selling points:

1. Full IP65 protection above and below the installation assures resistance to dust and moisture, making it robust for all weather conditions.
2. Constructed from non-corroding materials such as polycarbonate and acrylic, it's specifically designed to withstand coastal environments where salt and humidity are prevalent.
3. The CCT switch feature provides the flexibility to choose the perfect shade of white light, from warm to cool, ensuring the lighting always complements the space and occasion.

Lighting Styles - Here to help

We have knowledgeable staff waiting For your Call. Discuss your needs, check any technical details, Or ask for advice on any of our products.

Stamford UK - 01780 767617

Designed with practicality and longevity in mind. It's an energy-efficient lighting solution, with a 5-watt LED lamp that brightly emits 520 lumens, ideal for creating a well-lit outdoor space with a warm and inviting glow.

Additional features include:

- A long-lasting lamp life of over 30,000 hours, greatly reducing the need for replacements and maintenance.
- Compatibility with standard dimmers, allowing you to adjust the brightness to your preference, enhancing the user experience.
- An integral driver within the unit ensures a safe, water-resistant installation, making it reliable in various weather conditions.
- Comes pre-wired with 30cm of cable, facilitating a straightforward installation process.
- A 60° wide beam angle provides ample light spread, perfect for illuminating larger areas under soffits or canopies.
- Designed to fit ceilings ranging from 1mm to 30mm thick, offering flexibility in various installation scenarios.
- The downlight's dimensions and minimal void requirements (Diameter 55mm cut-out, Minimum Void Height 60mm) make it suitable for a range of spaces, ensuring it can be easily incorporated into most design schemes.
- The product comes with a 3-year manufacturer's warranty, giving you peace of mind regarding its quality and durability.

This downlight is an excellent choice for both residential and commercial settings, ensuring a seamless blend of functionality, energy efficiency, and design adaptability, especially in coastal areas where durability is key.

Cut-out Diameter: 55mm		Overall Diameter: 81mm	
Number Of Lamps		1	
Lamp Type		Long Life LED Light Source	
Lamp Lumens		520	
Dimmable?		Yes - on standard dimmer (TRIAC or leading edge)	
Total Wattage		5w	
Height		47mm	
Diameter		81mm	
Depth/Projection		2mm	
Suggested Void Depth		60mm	
Cut-Out Diameter		55mm	
Construction		ABS Polycarbonate	
Wiring Details		Class 2 - Double Insulated - Requires no Earth Connection	
IP Rating		IP65	
Driver		Includes integral driver/transformer suitable for 230 - 240v supply	

Product

LED Downlight Full IP65 Protection Above & Below Soffits - Corrosion-Resistant & CCT(Ref:54969)

Your Name

Your Email

Your Tel

Question

SUBMIT QUESTION

Will this lights be guaranteed in a costal area?
Yes, this is suitable for coastal areas.

What are the black bezel's made out of. Are they steel or ABS polycarbonate. I live in Guernsey in the Channel Islands near the coast and need something durable.
The bezels are polycarbonate so would be ideal for the coast as they will not corrode.

How is the CCT controlled? And it is good to be installed on the soffit 5 meter above ground level?
It contains an integral switch to change the CCT (colour temperature) - this is on the inside of the fitting. It should be fine at a height of 5m.

Availability: Typically dispatched in 2-4 days

We offer free delivery on orders over £80 to most UK Mainland Addresses

Product Code	Product Title	Price	Quantity
LED Downlight with White Bezel			
SAM108763 In Stock - Quick Dispatch	Soffit CCT LED Downlight - Full IP65 Protection	£16.20 £13.50 exc VAT	

Optional coloured bezels

SAM95204	Black bezel for CCT IP65 Downlight	£3.50 £2.92 exc VAT
SAM95203	Polished Chrome bezel for CCT IP65 Downlight	£3.50 £2.92 exc VAT
SAM95202	Satin Nickel bezel for CCT IP65 Downlight	£3.50 £2.92 exc VAT
SAM78419	Antique brass bezel for CCT IP65 Downlight	£4.75 £3.96 exc VAT

Questions?
Try our customer services section or call us on 01780 767617.

Related Categories



RECESSED BATHROOM DOWNLIGHTS



CCT DOWNLIGHTS COLOUR SELECTABLE



COASTAL LIGHTING - CORROSION RESISTANT



INNOVATIVE LED LIGHTS FOR USE OUTDOORS



SOFFIT & EAVES LIGHTING



CEILING MOUNTED EXTERIOR DOWNLIGHTS