EXISTING LAGOON 1

FFL 5.050 (varies)

TO DITCH

TO DITCH

TO DITCH

TO DITCH

New Ditch

New Ditch

New Ditch

Permeable Area

Notes

1. This drawing to be read in conjunction with all relevant Architects and Engineers drawings and specifications.
2. Dimensions are in millimetres unless noted otherwise.
3. Original topographic survey undertaken by Shaw Colegate.
   For full topographic survey information see Shaw Colegate drawing No. 10417-TP
   All levels based on Ordnance Survey by GPS.
4. Existing levels shown thus: +5.77

Key :

1. Roof Area to Lagoon = 6775m² (Syphonic Drainage by Fullflow Ltd)
2. Impermeable Pavement to Lagoon = 5925m² (Via Packaged Pumping Station)
3. Impermeable Road to New Ditch
4. Impermeable Road to New Ditch
5. Impermeable Pavement to Lagoon = 1260m²
6. Permeable Car Park = 4250m²

REV	DESCRIPTION	CHECKED	DATE

Archibald Shaw

[redacted]

CLIENT
Barfoots of Botley

PROJECT
New Packhouse
Sefter Farm, Pagham
Surface Water Catchments

DRAWN BY	CHECKED BY	DESIGNED BY
PF	VC	PF
SCALE @ A1	©DATE	STATUS
1:400	Nov. 2017	Preliminary
JOB NO.	DRAWING NO.	REVISION
28725	300	P1

ARUN DISTRICT COUNCIL FI/17/1000