




Planning Application: P/136/22/HH
33 West Front Road, Pagham PO21 4SZ

Schedule of materials and finishes

KEY	Material	Product	Colour	Image
1. Flat roof	Rubber	EPDM and edging trims	Black EPDM with Anthracite Grey (RAL 7016) EPDM edging trims	
2. Metal framed windows	Aluminum frame/Glass	Eurocell	Anthracite/Clear Glass	
3. Cladding - Light	Composite - Vertical orientation	Millboard Shadowline	Ashwood	
4. Cladding - Dark	Composite - Vertical orientation	Cladco	Charcoal	
5. Render	Silican render	K Rend	Causeway (grey)	
6. Downpipe	uPVC	Floplast	Anthracite grey	
7. Gutter	uPVC	Floplast	Anthracite grey	
8. Rainwater hopper	uPVC	Floplast	Anthracite grey	
9. Coping	Aluminum	Alumasc	Anthracite grey	

10. PV Panels	Monocrystalline	400W panel	Black	
11. Rooflights	Wood/Glass		Black/Clear Glass	
12. Man made slate	Fibre Cement	600 x 300 Cedral	Black - to match existing	
13. Soffit and eaves	uPVC	Eurocell	Anthracite Grey	
14. Front door	Composite	Eurocell Dales	Blue	
15. External steps	Bricks/concrete		neutral	
16. Planters	Timber	Treated sleepers	Pine	
17. Reused stain glass windows	Glass/Lead/uPVC		Black frame	
18. Metal sliding doors	Aluminum frame/Glass	Aluna	Anthracite/Clear Glass	

19. External bench	Treated Timber	Custom built	Pine	
20. Existing condition	Material as per existing condition	NA	NA	

Note - Products are provided as a guide, manufacturers could be updated.