



1. All dimensions are in metres unless stated otherwise.
2. Do not scale from this drawing. Only written dimensions are to be used.
3. Site layout based on Cooper Baillie Planning Layout, drawing number CB_84-139_001 Rev G dated 16th August 2021.
4. Topographical survey based on MK Surveys layout, drawing number 22496-2 dated January 2021.
5. Layout review is subject to receipt of finalised layout proposal and the final highway layout design will be subject to the outcome of consultation with West Sussex County Council.

1. Assumed speed limits:
 - Roads Within Development = 20mph
 - *Speed Control Bends = 12mph*
(Subject to agreement with Client/Planning).
2. Junction visibility requirements:
 - For 20mph road = $2.4m \times 25m$ (Manual for Streets).
3. Forward visibility requirements:
 - 25m for 20mph (Manual for Streets).
 - 14m for 12mph (Manual for Streets).
4. Landscaping & any External Works Fencing (i.e. Picket Fencing within property curtilage) to be kept below 600mm in height where located within visibility splay.

Site Boundary	
Potential School, care home or residential site under separate planning application	
Junction Visibility Spays (25m)	
Forward Visibility Spays (14m)	
Forward Visibility Spays (25m)	

[illegible]

Rev.	Date	Details	By	Chkd	Appd
------	------	---------	----	------	------

Taylor Wimpey

Drawing Title:-
**VISIBILITY SPLAY
ANALYSIS**

Date: August 2021		Scales: 1:1000 at A1	
Drawn: TS	Checked: TS	Approved: TS	

Drawing No. WSC/E4775/01/004

FOR INFORMATION ONLY



T: 01256 769269 E: mail@rcpconsultants.co.uk W: rcpconsultants.co.uk