

SAUNDERS SPECIALISED SERVICES LTD

Unit 25 St. James Industrial Estate,
Westhamphett Road, Chichester, PO19 7JU
Tel: (01243) 530714 Fax: (01243) 530728
E-mail: sales@saunders-heating.co.uk
Web Site: www.saunders-heating.co.uk

**Industrial and Commercial Heating, Ventilation,
Process, Air-Conditioning and Electrical Engineers**

QUOTATION : RWS/140507/PAGHAM

Proposal

Room Volume	7.5m x 4.7m x 3m = 105.75m ³
Air Change Rate	12 Ac/Hr
Airflow	1269m ³ /hr (0.35 m ³ /second)

The entire room volume is used as the hood is within the open space.

Supply and install one number 1800mm x 1000mm x 600mm kitchen canopy in the newly proposed kitchen area as discussed on site.

The hood will have 50mm x 25mm condense channel complete with safe edge, division plate and baffle style grease filters all made from 304 grade stainless steel.

Supply and install the ductwork to connect to the roof extract fan through the window panels.

Supply and install on the roof, one number VES Andover air handling unit with an airflow of 0.35m³/second @ 100 Pascal's external resistance.

The unit will have a grease filter, bag filter, carbon filter and extract fan and be constructed from 25mm square tubular frames with a external powder coated paint.


The unit dimensions (which will need confirming suitable for the roof) will be 2775mm Long x 925mm Wide x 760mm High.



Directors: Robert Saunders B.Eng (Hons), Eric Humphrey - Est. 1963



VAT Registration No. 193 6124 57



Registered in England No. 1151246

SAUNDERS SPECIALISED SERVICES LTD

Unit 25 St. James Industrial Estate,
Westhampnett Road, Chichester, PO19 7JU
Tel: (01243) 530714 Fax: (01243) 530728
E-mail: sales@saunders-heating.co.uk
Web Site: www.saunders-heating.co.uk

**Industrial and Commercial Heating, Ventilation,
Process, Air-Conditioning and Electrical Engineers**

Carry out electrical connections to the unit from a local supply. The unit is 415V but whether this is available will need to be confirmed prior to commencement.

Commission the unit on completion and set to work. Explain the unit to the operator and leave working.

Budget figure for the above, for the sum of £ 9,415.00 Plus VAT

Make up air may be needed. The final layout / design of the room will need to be determined before a final price can be given. A louvre in the main entrance door will most likely suffice.



Directors: Robert Saunders B.Eng (Hons), Eric Humphrey - Est. 1963



VAT Registration No. 193 6124 57



Registered in England No. 1151246