



Engineers Comments Regarding Surface Water Drainage

The applicant indicates that if the application is successful the site will drain surface water by infiltration. We are agreeable to this, however the design will need to be informed by winter infiltration tests in strict accordance with BRE365 and a full winter's groundwater monitoring. In addition, our records show that a foul sewer may cross this site, please consult Southern Water regarding this. If you are minded to approve the application please apply the following conditions to ensure that the development is adequately drained and does not increase flood risk elsewhere.

PCENG D2

“Development shall not commence, other than works of site survey and investigation, until full details of the proposed surface water drainage scheme have been submitted to and approved in writing by the Local Planning Authority. The design should follow the hierarchy of preference for different types of surface water drainage disposal systems as set out in Approved Document H of the Building Regulations, and the recommendations of the SuDS Manual produced by CIRIA. Winter groundwater monitoring to establish highest annual ground water levels and winter Percolation testing to BRE 365, or similar approved, will be required to support the design of any Infiltration drainage. No building / No part of the extended building shall be occupied until the complete surface water drainage system serving the property has been implemented in accordance with the agreed details and the details so agreed shall be maintained in good working order in perpetuity.”

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W SP1, W DM1, W DM2 and W DM3 of the Arun Local Plan. This is required to be a pre-commencement condition because it is necessary to implement the surface water drainage system prior to commencing any building works.

PCENG D4

“Development shall not commence until full details of the maintenance and management of the surface water drainage system is set out in a site-specific maintenance manual and submitted to, and approved in writing, by the Local Planning Authority. The manual is to include details of financial management and arrangements for the replacement of major components at the end of the manufacturer's recommended design life. Upon completed construction of the surface water drainage system, the owner or management company shall strictly adhere to and implement the recommendations contained within the manual.”

Reason: To ensure that the proposed development is satisfactorily drained in accordance with policies W DM1, W DM2 and W DM3 of the Arun Local Plan. It is considered necessary for this to be a pre-commencement condition to ensure that the future maintenance and funding arrangements for the surface water disposal scheme are agreed before construction commences.

And the accompanying informative:


INFORM D

“Infiltration rates for soakage structures are to be based on percolation tests undertaken in the winter period and at the location and depth of the proposed structures. The percolation tests must be carried out in accordance with BRE365, CIRIA R156 or a similar approved method and cater for the 1 in 10 year storm between the invert of the entry pipe to the soakaway, and the base of the structure. It must also have provision to ensure that there is capacity in the system to contain below ground level the 1 in 100 year event plus 40% on stored volumes, as an allowance for climate change. Adequate freeboard must be provided between the base of the soakaway structure and the highest recorded annual groundwater level identified in that location. Any SuDS or soakaway design must include adequate

groundwater monitoring data to determine the highest winter groundwater table in support of the design. The applicant is advised to discuss the extent of groundwater monitoring with the Council's Engineers. Supplementary guidance notes regarding surface water drainage are located here <https://www.arun.gov.uk/surfacewater> on Arun District Councils website. A surface water drainage checklist is available on Arun District Councils website, this should be submitted with a Discharge of Conditions Application."

Kind Regards

Sarah Burrow
Engineering Assistant



To: Engineers (Drainage)

**NOTIFICATION FROM ARUN DISTRICT COUNCIL
Town & Country Planning Act 1990 (as amended)
Town and Country Planning (Development Management Procedure) (England) Order 2015
Planning Permission**

APPLICATION NO: P/18/20/PL

Registered: 3rd March
2020

Site Address: Land west of Barton House Manor Park Pagham E2 9LJ

Grid Reference: 489446 98311

Description of Works: Change of use from highway land to residential use for the development of 4 No. 3 bed terraced houses with associated parking & access. This application affects the setting of a listed building.

The Council have received the above application. I shall be pleased to receive any observations you may wish to make.

[Click here to view the application details](#)

Should you have any comments to make, these should be sent by replying to this email by 02-APR-20.

You can also monitor the progress of this application through the Council web site:
www.arun.gov.uk/planning

Please be aware that any comments you may make will be available on our website so please do not insert personal details or signatures on your reply.

In the absence of a reply within the period stated, I shall assume that you have no observations to make.

The application will be determined having regard to the development plan policies (if any are relevant) and other material considerations. The development plan can be accessed via the website as can the leaflet which deals with material planning considerations.

Should the application go to appeal the Planning Inspectorate will publish any comments made to the Council on their website: www.planningportal.gov.uk/planning/appeals/ but they will protect personal details.

The officer dealing with this application is David Spring who can be contacted on telephone number [REDACTED]

Regards
Planning Officer

consultee_email
