



Highlights Floodlighting Ltd

Specialist Floodlighting Installation Contractors

Manor Farm Court, Manor Road, Lower Sundon, Bedfordshire LU3 3NZ



Vat Reg No: 727747108

Company Reg. No. 3895810

Pagham Football Club
Nyetimber Lane
Pagham
West Sussex
PO21 3JY

F.A.O. Mr Eric Nunn

1st September 2020
Estimate No. 8170M

ESTIMATE

Further to your recent enquiry, we take pleasure in submitting our estimate as follows:-

To take down and store/remove from site the 20 No. existing redundant 2000 watt floodlight luminaires from the 4 No. existing 18 metre high Towermaster floodlight columns.

To supply and install 16 No. Philips OptiVision MVP507 2000 watt asymmetric low glare floodlight luminaires complete with Tridonic Control Gear and Philips MHN-FC lamps.

The proposed installation will achieve an average maintained horizontal illuminance of 204 lux with a min/ave. uniformity factor of 0.68 and a min/max uniformity factor of 0.45.

This estimate is fully inclusive of the supply and installation of 4 No. new control gear cabinets and all associated materials to complete the above works.

To test out and supply commissioning reports on completion of works.

Estimated cost: -

The total installed power for the proposed installation is 33.90 kilo watts.

All works carried out in accordance with NICEIC regulations.

All works carried out in accordance with current Health & Safety regulations.

Insurance details, Health & Safety Policy and Method Statement will be available should we be successful in our quotation.

We trust the enclosed is of interest but please do not hesitate to contact us should you require any further information or assistance.

Assuring you of our best care and attention at all times.

Yours faithfully

Mark Peckham
DIRECTOR