



## Surface Water Drainage Proposal Checklist

This 'Surface Water Drainage Proposals Checklist' has been designed to clearly define Arun District Council's and Chichester District Council's expectations and requirements for any surface water drainage proposals, submitted for appraisal by the council's Engineers, during the planning process.

Please be aware that it is in your interest to provide all of the requested information, as this will allow the council's Engineers to quickly and efficiently review your proposals. The omission of any requested information may lead to delays in the planning process.

This document will be of help to any applicant, or drainage consultant, preparing to submit a 'Discharge of Conditions Application' relating to surface water drainage conditions. Alternatively, it can also be used earlier in the planning process, if the applicant wishes to avoid pre-commencement conditions relating to surface water drainage. The Town and Country Planning Regulations now require pre-commencement conditions to have the prior agreement of the applicant regarding their wording and use. Therefore, if you wish to avoid pre-commencement conditions, in relation to surface water drainage, you will need to submit proposals that provide the information requested in this checklist and also align with the requirements of the following documents:

West Sussex Policy for the Management of Surface Water (WSSC)

'Supplementary Requirements for Surface Water Drainage Proposals'. (Arun DC) ~~✗~~

'Supplementary Requirements for Surface Water Drainage Proposals'. (Chichester DC)

By submitting all of the information requested by this checklist you will enable the council's Engineers to determine whether your proposals follow the hierarchy for sustainable drainage and will adequately drain the site.

Please be aware that it will be difficult for the council's Engineers to undertake a timely assessment of your application if you fail to provide any of the information requested.



## Surface Water Drainage Proposal Checklist

| Ground Investigation Results                                                  |                                  |                                     |    |
|-------------------------------------------------------------------------------|----------------------------------|-------------------------------------|----|
| Results Required                                                              | Results Provided?                |                                     |    |
| Winter groundwater monitoring results (Please refer to guidance note 1 below) | Yes                              | <input checked="" type="checkbox"/> | No |
| Period of winter groundwater monitoring Note 1                                | From                             | FEB 21 / YYYY                       |    |
|                                                                               | To                               | FEB 21 / YYYY                       |    |
| Maximum recorded groundwater level                                            | 2 mAOD<br>mBGL                   |                                     |    |
| Winter infiltration test results Note 2                                       | Yes                              | <input checked="" type="checkbox"/> | No |
| Date of winter infiltration testing                                           | FEB 21 / YYYY                    |                                     |    |
| Details of the location and depth of the infiltration testing Note 3          | Yes                              | <input checked="" type="checkbox"/> | No |
| Minimum infiltration rate Note 4                                              | LESS THAN $1 \times 10^{-6}$ m/s |                                     |    |

### Guidance Notes

1. A full winters groundwater monitoring should be undertaken, (October to March inclusive) to enable the peak annual groundwater levels to be established. The extent of winter monitoring for developments of less than 5 properties should be discussed with the council's Engineers.
2. Infiltration testing should be undertaken during the wet winter months (typically January) and in line with BRE365, or a similar approved method. Tests should be repeated 3x, to replicate saturated ground conditions. Please note that infiltration testing is to be carried out at a time and depth agreed with the Councils engineers.
3. Infiltration testing should be undertaken at the location and depth of any proposed infiltration structures. This must be above the maximum recorded groundwater level in that vicinity.
4. The minimum infiltration rate obtained at the location and depth of the proposed infiltration structures should be used to inform the design of the structures.

| Proposed Method of Surface Water Disposal                                                               |     |                                     |    |
|---------------------------------------------------------------------------------------------------------|-----|-------------------------------------|----|
| Infiltration                                                                                            | Yes | <input type="checkbox"/>            | No |
| On-site, via soak-away structures                                                                       | Yes | <input checked="" type="checkbox"/> | No |
| If on-site infiltration is not to be used, has justification for this been provided? Note 5             | Yes | <input checked="" type="checkbox"/> | No |
| Attenuation (on-site) with a restricted discharge to a watercourse or, or adjacent to, the site         | Yes | <input checked="" type="checkbox"/> | No |
| Attenuation (on-site) with a restricted discharge to a surface water sewer on, or adjacent to, the site | Yes | <input type="checkbox"/>            | No |
| Attenuation (on-site) with a restricted discharge to a foul water sewer on, or adjacent to, the site    | Yes | <input type="checkbox"/>            | No |

### Guidance Notes

5. If on-site infiltration is not being used to drain the site you will need to provide evidence that demonstrates on-site infiltration is unviable.

Version 3.0 (20.11.2019)

| Drainage Design: Supporting Calculations        |                                                                                                                                                                                                                                                                 |                                                                        |                        |  |
|-------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------|------------------------|--|
| Calculations Required                           |                                                                                                                                                                                                                                                                 |                                                                        | Calculations Provided? |  |
| Infiltration Structures                         | Half-drain time for 10 year event (plus climate change allowance)                                                                                                                                                                                               | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>    | Hours                  |  |
|                                                 | Half-drain time for 100 year event (plus climate change allowance)                                                                                                                                                                                              | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>    | Hours                  |  |
|                                                 | Calculations demonstrating that the 1 in 100 year event, plus climate change allowance can be accommodated on-site. <small>Note 7</small>                                                                                                                       | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>    |                        |  |
|                                                 | Lowest base level of infiltration structure                                                                                                                                                                                                                     | mAOD <input type="checkbox"/> mBGL <input checked="" type="checkbox"/> |                        |  |
|                                                 | Has the design sought to provide treatment of potential contaminants? E.g. hydrocarbons.                                                                                                                                                                        | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>    |                        |  |
| Attenuation and Subsequent Restricted Discharge | Pre-development run-off rate calculations                                                                                                                                                                                                                       | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>    | 0.4 - 1.2 l/s          |  |
|                                                 | Proposed discharge rate <small>Note 6</small>                                                                                                                                                                                                                   | THE WALLINGTON MIN RATE 5 l/s                                          |                        |  |
|                                                 | Calculations demonstrating that the 1 in 100 year event, plus climate change allowance can be accommodated on-site. <small>Note 7</small>                                                                                                                       | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>    |                        |  |
|                                                 | Has the design sought to provide treatment of potential contaminants? E.g. hydrocarbons.                                                                                                                                                                        | Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>    |                        |  |
|                                                 | If your proposed scheme incorporates any impermeable lined attenuation features we require calculations to demonstrate that appropriate resistance to floatation (due to groundwater levels) is catered for in the design                                       | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>    |                        |  |
|                                                 | If you propose discharging into or altering an ordinary watercourse; have you sought Ordinary Watercourse/Land Drainage Consent? <small>Note 8</small>                                                                                                          | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>    | NOT YES                |  |
|                                                 | If discharging to a watercourse, piped system or the sea, has the proposed drainage network been modelled against predicted top water levels for the 1 in 100 year storm event plus climate change allowance, within the existing system? <small>Note 9</small> | Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>    |                        |  |

#### Guidance Notes

- Any proposed discharge rate must be less than, or equal to, the pre-development rate. Greenfield sites must use the mean flow rate (Qbar) and be based upon the area occupied by the development, ignoring significant open spaces. Please note that the minimum acceptable discharge rate is 2l/s when using formal flow control devices, unless otherwise agreed. Additionally, if you are developing a brownfield site, we expect you to provide fully detailed plans of the existing surface water drainage arrangements on site, including impermeable areas, gullies, outfalls, pipes & diameters, manholes, etc. We generally seek 50% betterment in terms of run off from brownfield sites.
- The appropriate factor of safety from the table below must be applied to your calculations to ensure your design is fully in accordance with CIRIA R156/ CIRIA C753.

LOWEST UNKNOWN BUT DEERED TO HAVE ADEQUATE FREE BOARD SUBJECT TO DISCUSSION WITH LPA.

| Factor of Safety Table                  |                            |         |                                                     |         |                                             |         |
|-----------------------------------------|----------------------------|---------|-----------------------------------------------------|---------|---------------------------------------------|---------|
| Size of Area to be Drained              | Consequences of failure    |         |                                                     |         |                                             |         |
|                                         | No damage or inconvenience |         | Minor inconvenience, e.g. surface water on car park |         | Damage to buildings or structures or roads. |         |
|                                         | Cv=1.0                     | Cv=0.75 | Cv=1.0                                              | Cv=0.75 | Cv=1.0                                      | Cv=0.75 |
| <100 m <sup>2</sup>                     | 1.5                        | 2       | 2                                                   | 3       | 10                                          | 13      |
| 100m <sup>2</sup> to 1000m <sup>2</sup> | 1.5                        | 2       | 3                                                   | 4       | 10                                          | 13      |
| >1000m <sup>2</sup>                     | 1.5                        | 2       | 5                                                   | 6.5     | 10                                          | 13      |

8. Ordinary Watercourse/Land Drainage Consent will need to be sought, ideally in parallel with planning permission, if you propose discharging into, culverting or altering a watercourse.
9. Modelling is required to ensure that problems, such as surcharged outfalls, are addressed.

| Plans/Drawings/Diagrams                                                                                                                                                                                                      |           |                                     |    |                                     |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|-------------------------------------|----|-------------------------------------|
| Required                                                                                                                                                                                                                     | Provided? |                                     |    |                                     |
| Plan detailing the location of groundwater monitoring and infiltration testing                                                                                                                                               | Yes       | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |
| Detailed drainage layout plan <small>Note 10</small>                                                                                                                                                                         | Yes       | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |
| Construction detail plans <small>Note 11</small>                                                                                                                                                                             | Yes       | <input type="checkbox"/>            | No | <input checked="" type="checkbox"/> |
| Exceedance flow route plans <small>Note 12</small>                                                                                                                                                                           | Yes       | <input type="checkbox"/>            | No | <input checked="" type="checkbox"/> |
| Impermeable area plan                                                                                                                                                                                                        | Yes       | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |
| If ground levels are being raised $\geq 300\text{mm}$ above existing levels and is unavoidable, have fully detailed plans been provided, together with drainage proposals, to address any potential drainage related issues. | Yes       | <input checked="" type="checkbox"/> | No | <input type="checkbox"/>            |

Geotextile

NOT req.

### Guidance Notes

10. Drainage layout plans should include:
  - All surface water drainage pipes labelled with; diameters, pipe materials, falls and invert levels.
  - All infiltrating and attenuating structures (including permeable paving) labelled with; dimensions, invert and cover levels.
  - All manholes labelled with; cover levels, invert levels, cover types detailed.
  - All silt traps clearly labelled with sump depths.
  - Control structures with outflow rates and invert levels.
  - Proposed/existing levels of any areas subject to ground raising, together with suitable measures/detailed drawings for the associated management of surface water runoff. Please note that ground raising should be avoided unless there are exceptional circumstances.
11. Site specific construction detail plans should be supplied if your proposed drainage scheme includes any of the following elements: pipe bed and surround; infiltrating structures; attenuating structures; manholes; catch-pits/silt traps; control devices; permeable paving; headwalls.
12. Unless specifically requested by the council's drainage engineers 'Exceedance Flow Route Plans' are only required for developments of more than 5 residential properties or more than 0.5ha of commercial development.

Version 3.0 (20.11.2019)